FORM (REV	( PTO-139 10-95)	0 U.S DEPARTMENT OF O	RK OFFICE ATTORNEYS DOCKET NO.										
		TRANSMITTAL LETTER TO T DESIGNATED/ELECTED OF	FFICE (DO/EO/US)	3699-2-PUS U.S. APPLICATION NO. (If known, see 35 CFR 1.5) 09/646141									
n men	D3.11.000	CONCERNING A FILING UN											
INTE	RNATIO	NAL APPLICATION NO.	INTERNATIONAL FILING DATE	PRIORITY DATE CLAIMED									
		PCT/US97/08842	05 June 1997	14 March 1997									
TITLE	TITLE OF INVENTION "COPY PROTECTABLE OPTICAL MEDIA DEVICE AND METHODOLOGY THEREFOR"												
APPL	APPLICANT(S) FOR DO/EO/US  McLAUGHLIN et al.												
Appli	Applicant herewith submits to the United States Designated/Elected Office (DO/EO/US) the following items and other information:												
1.	[X]												
2.	[]	This is a <b>SECOND</b> or <b>SUBSEQUENT</b> submission of items concerning a filing under 35 U.S.C. 371.											
3.	[X]	This express request to begin national examination procedures (35 U.S.C. 371(f))) at any time rather than delay examination until the expiration of the applicable time limit set in 35 U.S.C. 371(b) and PCT Articles 22 and 39(l).											
4.	[X]	A proper Demand for International Preliminary Examination was made by the 19th month from the earliest claimed priority date.											
5.	[X]	A copy of the International Application as filed (35 U.S.C. 371(c)(2))											
		a. [ ] is transmitted herewith (req	uired only if not transmitted by th	e International Bureau).									
		b. [] has been transmitted by the	International Bureau										
6.		7.	es Receiving Office (RO/US).										
<b>-</b> 6.	F 1	c. [X] is not required, as the application was filed in the United States Receiving Office (RO/US).  A translation of the International Application into English (35 U.S.C. 371(c)(2)).											
7.	[X]		• ,	`` <i>'</i> '									
<del></del> .	[/]	Amendments to the claims of the International Application under PCT Article 19 (35 U.S.C. 371(c)(3)).  a. [ ] are transmitted herewith (required only if not transmitted by the International Bureau).											
Tribing - Carlos				ne memational Buleau).									
		b. [] have been transmitted by the International Bureau.											
		c. [] have not been made; however, the time limit for making such amendments has NOT expired.											
Ū ≟ 8.	r 1	d. [X] have not been made and will not be made.  A translation of the amondments to the plaints and an DCT Article 10 (25 U.S.C. 271(a)(2))											
		A translation of the amendments to the claims under PCT Article 19 (35 U.S.C. 371(c)(3)).											
9. 10.	[X]	An oath or declaration of the inventor(s) (35 U.S.C. 371(c)(4)).  A translation of the annexes to the International Preliminary Examination Report under PCT Article 36 (35 U.S.C. 371(c)(5)).											
==:				eport under PCT Article 36 (35 U.S.C. 371(c)(5)).									
		16. below concern documents or informa											
11.		An Information Disclosure Statement under 37n CFR 1.97 and 1.98.											
12.	[X]	An assignment document for recording. A separate cover sheet in compliance with 37 CFR 3.23 and 3.31 is included.											
13.	[]	A FIRST preliminary amendment.											
14.	[]	A SECOND or SUBSEQUENT preliminary amendment.											
15.	[]	A substitute specification.											
16.	[]	A change of power of attorney and/or address letter.											
17.	[X]	Other items or information:	#5V55500 MA										
		Petition to Correct an Obvious Error and	to DATE OF DEPO	L" MAILING LABEL NUMBER: EL417658322 SIT: September 13, 2000									
		Revive an Unintentionally Abandoned Ap	THE UNITED S ADDRESSEE" ABOVE AND IS	TIFY THAT THIS PAPER OR FEE IS BEING DEPOSITED WITH TATES POSTAL SERVICE "EXPRESS MAIL POST OFFICE TO SERVICE UNDER 37 CFR 1.10 ON THE DATE INDICATED ADDRESSED TO THE ASSISTANT COMMISSIONER FOR PCT, WASHINGTON, D.C. 20231.									
			TYPED OR PRI	NTED NAME: JANICE MESSER									
			SIGNATURE	Marie Money									

# 430 Rec'd PCT/PTO 1 3 SEP 2000

U.S. APPLICATION TO 16 known, see 37 CFE1.5) INTERNATIONAL APPLICATION NO. PCT/US97/08842						ATTORNEY DOCKET NUMBER 3699-2-PUS						
17. [X] The following fees		CALCULATIONS PTO USE ONLY										
BASIC NATIONAL FEE	BASIC NATIONAL FEE (37 CFR 1.492(a)(1)-(5)):											
Search Report has bee												
International prelimina												
No international prelin												
Neither international p international search fe	i.											
International prelimina and all claims satisified												
	\$	96.00										
Surcharge of \$130.00 for fur months from the earliest clai	\$	130.00										
CLAIMS	NUMBER FILED		NUMBER EXTRA	RATE								
Total Claims		- 20 =	22	x \$18.00	\$ 396.00							
Independent Claims	21 ENT CLAIMS(S) (if applica	- 3 =	18	x \$78.00	\$ 1,404.00							
MULTIFLE DEFEND	ENT CLAIMS(S) (II applica		TAL OF ABOVE CALCU	+ \$260.00	\$	2,026.00						
Reduction of ½ for filing by		\$	2,020.00									
Note 37i CFR 1.9, 1.27, 1.2	also be filed	\$										
- man 1	UBTOTAL =	\$										
Processing fee of \$130.00 formonths from the earliest claim	\$											
	\$											
Fee for recording the enclose appropriate cover sheet (37)	\$	40.00										
			TOTAL FEES E	NCLOSED =	\$	2,066.00						
	An	nount to be: refunded	\$									
						charged	\$					
a. [X] A check in the												
b. [ ] Please charge my Deposit Account No in the amount of \$ to cover the above fees. A duplicate copy of this sheet is enclosed.												
c. [X] The Commissioner is hereby authorized to charge any additional fees which may be required, or credit any overpayment to Deposit Account No. 19-1970. A duplicate copy of this sheet is enclosed.												
NOTE: Where an appropriate time limit under 37 cfr 1.494 or 1.495 has not been met, a petition to revive (37 cfr 1.137(a) or (b)) must be filed and granted to restore the application pending status.												
SEND ALL CORRESPONDENCE TO:												
SHERIDAN ROSS P.C.  1560 Broadway, Suite 1200  Denver, Colorado 80202-5141  Telephone: (303) 863-9700  Joseph E. Kovarik												
Facsimile: (303) 863-0223	Facsimile: (303) 863-0223  Registration No. 33,005											

20

25

09/646/4/ 03 Recd PCT/FTO 13 SEP 2000

# COPY PROTECTABLE OPTICAL MEDIA DEVICE AND METHODOLOGY THEREFOR

#### FIELD OF INVENTION

The present invention broadly relates to data storage media for use with optical scanning machines, which data storage media are adapted to limit access to information stored thereon. More particularly, the present invention concerns optical disks for use in an optical readout system of a computer to limit continual or repeated unrestricted access to stored data by the optical readout system. A method is also provided for limiting access to data stored in an optical medium environment.

#### BACKGROUND OF THE INVENTION

The computer industry has long been plagued by the illegal misappropriation of software products. Software Publisher's Association (SPA), an organization with devotes significant resources to tracking analyzing piracy problems, has determined that in 1994 alone the personal computer software industry lost in excess of \$8 billion due to illegal copying of business application software. The SPA further estimated that virtually half of the business software in use in 1994 was pirated, and this estimate does not include the illegal copying of operating systems, education, entertainment or personal productivity software. The piracy problem is particularly acute in more developed markets such as the United States.

Many approaches have been implemented by software producers in an effort to combat piracy. Some of these approaches include encryption, special data formatting complex installation procedures, and passwords, to name only a few. Unfortunately, end user resistance to these anti-piracy schemes has been high because they are plaqued

15

20

25

30

35

by one or more limitations, such as an inability to "try before you buy", restrictions on the generation of legitimate back-up copies, and password protection techniques which fail once the password is divulged or discovered. The inability of copy protection schemes to win end-user acceptance has been so extreme that many publishers have simply abandoned the effort, choosing instead to rely on the integrity of their customers to abide by copyright laws.

The of software misappropriation is rampant irrespective of whether the data storage medium is magnetic or optical. Magnetic storage disks are particularly susceptible to piracy. Commercially available magnetic the conventional floppy disk, such as read/write/erase memory devices in which data is stored in a magnetizable surface layer as discrete patterns of magnetism. Information is stored and retrieved by a read/write head which contains a coil wound around an iron core.

While the magnetic recording medium remains the most popular, there has been a growing trend in recent years to utilize an optical medium environment for the storage and retrieval of data. The reason for this trend is readily apparent. A commercially available magnetic floppy disk is only capable of storing 1.44Mb of data, whereas an optical CD-ROM of the same size can have a capacity in excess of 600Mb.

In a typical optical disk for use in a computer's optical readout system, data is stored as a series of lands and pits. This is accomplished by stamping along spiral tracks on a transparent plastic disk, overlaying this with a reflective coating, and thereafter superimposing a protective layer over this coating. Light from a semiconductor laser is focused onto either the lands or pits from below and the reflected light impinges upon a

20

25

30

photodetector which converts the presence or absence of the pits into a binary electrical signal. Because the focused laser spot is so minute, the amount of information that can be stored onto the surface of the disk is immense.

- Adjacent tracks need only be spaced apart by approximately .6µm and, hence, 20,000 tracks may be available on a conventional 120 mm diameter (5 inch) optical disk. The electrical signals delivered to the optical readout system correspond to the magnitude of the
- reflected light which either increases or decreases due to interference and/or diffraction by the preformatted data structures.

In the 1970's, researchers began attempting to encode information on optical disks with lasers, and the video disk was subsequently developed. In the 1980's, more sensitive materials that could be encoded with a low power diode laser were developed. These diode lasers, operating at a wavelength of approximately 800 nm, are now universally employed to read audio and computer CD's. Following the advent of compact disks which are capable of being read with a laser diode, researchers have now endeavored to develop a marketable compact disk upon which data can be recorded by an end user. The benefit of this capability, as discussed above, is that optical laser recording provides a much higher information density than magnetic recording.

Presently, there is a write once and read many times (WORM) compact disk. This compact disk utilizes a dye that irreversibly changes state when exposed to a high power laser diode and maintains this state when read with a low power reading laser. As such, detection of the encoded data by the optical readout system does not affect the encoded data.

It is anticipated that the next generation of optical disks will be capable of being written on, read, erased and

10

15

20

25

30

35

rewritten on, etc. many times, similar to a magnetic disk. A photochromic material, or chromophore, is attractive for this purpose. Photochromism is the phenomenon whereby the absorption spectrum of a molecule or crystal changes reversibly when the material is irradiated by light possessing certain wavelengths. Thus, for example, a colorless compound may change its molecular state to a quasi-stable colored state when radiated by ultraviolet (UV) light, yet be returned to the colorless state upon exposure to visible light. Both organic and inorganic materials which exhibit these properties have been known for years.

Recently, photochromic compounds have attracted much attention in the field of optical recording. As discussed in Jun'Etsu Seto, Photochromic Dves, the photochromic materials initially studied for such an application did not have significant sensitivity in the infrared region near 800 nm, the wavelength region of conventional laser diodes. Seto recognizes, however, that a specific class photochromic compounds, known as spiropyrans, can be manipulated to exhibit improved sensitivity in the infrared region. Specifically, Seto discusses a class of photochromic spiropyrans with benzothiopyran units in the molecular framework and concludes that the synthesized spirobenzothiopyran is well suited to the requirements of erasable optical recording media for systems conventional laser diodes.

Another dye of the spiropyran class, having the chemical composition 6-nitro-1'3'3'-trimethylspiro[2H-1-benzothiopyran-2,2'-indoline], or 6-nitro-1-SBIPS for short, is discussed in Tarkka, Richard U., Talbot, Marc E., et al., "Holographic Storage in a near-ir sensitive photochromic dye", Optic Comm. 109, 54-58 (1994). This article discusses the use of 6-nitro-1-S-BIPS for use in the holography field wherein the dye becomes colored when

10

15

20

25

30

35

exposed to light having a wavelength of 780 nm. The film returns to a quasiclear state upon exposure to an ultraviolet light source at 337 nm.

It is anticipated, based on these recent developments, that the conventional magnetic disk will eventually become obsolete due to the recent developments in optical storage technology. Concurrent with this anticipated phaseout of magnetic disks will be a need to adequately address the piracy issues which have for so long plagued the software that the illegal misappropriation industry 50 proprietary rights can be thwarted. Accordingly, while past research has concentrated on utilizing photochromic materials for the recording of information on compact disks, the present inventors have realized that similar photochromic materials may also be used to protect the compact disk against illegal copying and distribution. addition, the present inventors have also recognized that certain other photoreactive materials, as well as oxygen reactive materials, may be employed for this purpose. is, compounds such as these may be used to deny access to a specially coated compact disk beyond one or more authorized uses. That is, such compounds, when applied as a coating on a disk, operate to effectively change its light transmissive properties upon exposure to a low power reading laser, thereby darkening the coating on the disk and rendering data undetectable by an optical readout system. Moreover, the inventors have also recognized other optical media data protection techniques for the present invention that also address the unrestricted duplication of information as discussed hereinabove.

#### SUMMARY OF INVENTION

It is an object of the present invention to provide a new and useful optical medium, such as an optical disk, and system therefor which is adapted for use with an optical

10

15

20

25

30

35

readout system of, for example, a computer, wherein the readout system includes a light source operative to produce an interrogating beam of light for reading data structures on the optical medium.

Another object of the present invention is to provide such an optical medium which is particularly adapted to prevent unrestricted access to encoded information thereon by an optical readout system, wherein the information may be, for example, graphical data, video data, audio data, text data, and/or a software program.

Another object of the present invention is to use the error detection capabilities of a conventional optical medium reader for: (a) determining a status of an optical medium provided by the present invention, and/or (b) verifying an object or person as authentic. That is, it is an object of the present invention to use the errors detected on the optical medium for (a) and/or (b) above. For example, the total number of errors detected in a predetermined area of the optical medium, the density of the errors detected in a predetermined location of the optical medium, and/or the pattern of errors in a predetermined area of the optical medium provides, according to the present invention, sufficient information for (a) and/or (b) above.

Another object of the present invention is to provide verification or authentication of information provided on or with the novel optical medium of the present invention. For example, the present invention may be used for verifying the authenticity of an optical disk having an audio and/or multimedia presentation thereon. Additionally, when the optical medium of the present invention is incorporated into, for example, a financial transaction card, the card can be verified as authentic.

Another object of the present invention is to provide verification or authentication of a user that is, for

10

15

20

25

30

35

example, desirous of making an electronic financial transaction such as on the Internet.

A further object of the present invention is to provide a new and useful optical disk which is relatively easy to manufacture without substantial increases in costs.

Yet another object of the present invention is to provide a methodology of limiting access to information stored on an optical medium for use in a computer's optical readout system.

Still a further object of at least some embodiments of the present invention is to provide an optical disk which is particularly constructed so that an end user is unaware of the disk copy protection features until after they have been performed.

A first collection of embodiments of the present invention accomplishes these objectives by providing an article of manufacture (e.g., an optical disk) that is adapted to be encoded with data and further adapted so that duplication of the data by an optical scanning machine (i.e., an optical readout system) may be restricted. article of manufacture comprises a substrate fabricated from a selected material, with a surface thereof provided with the data. A reactive compound is formed as a coating on at least a portion of the substrate surface and the reactive compound operates to change from an optically transparent state to an optically opaque state in response to irradiation for an accumulated duration of time by infrared light having desired characteristics, thereby to prevent light from the optical scanning machine from penetrating the reactive compound and to render the data undetectable by the optical scanning machine.

More particularly, an optical disk is provided which is adapted for use in an optical readout system of a computer wherein the optical readout system includes a light source operative to produce an interrogating beam of

15

20

25

30

35

light for reading data structures. Broadly, the optical disk according to the first collection of embodiments of the present invention includes an inner layer having an upper surface and a lower surface, with the lower surface thereof encoded with information stored as a plurality of data structures that are readable by the interrogating beam of light. The outer layer is disposed in a confronting relationship with the lower surface, and a film of a reactive compound is superimposed over at least some of these data structures. The reactive compound is selected to be of a type which is operative to change physical characteristics in response to a selected stimulus, thereby to affect readability of the data by the interrogating beam.

Preferably, the optical disk includes a layer of reflective material interposed between the lower surface and the reactive compound. This reactive compound may be supported on a lower surface of the disk's second layer and have a thickness of approximately 2-5 microns or, alternatively, it may be interposed between the lower surface and the disks outer layer. The lower surface is preferably contoured to include a sequence of pits and lands which define the plurality of data structures, with the reactive compound superimposed over at least some of these pits and lands.

The selected stimulus to which the reactive compound responds is an ambient environment selected to be either visible light, infrared light, light and oxygen, or simply air. Where the stimulus is light alone, the reactive compound may be a photoreactive material and preferably one selected from a spiropyran class of photochromic compounds. One such compound may be 6-nitro-1'3'3'-trimethylspiro-[2H-1benzothiopyran-2,2'-indoline], or 6-nitro-1-S-BIPS for short. Such a photochromic compound is operative to change from an optically opaque or darkened condition in response

10

15

20

25

30

35

to an interrogating beam wavelength of approximately 780 nanometers (nm) and thereafter return to an optically transparent condition in response to a irradiation by a beam of light having a wavelength of approximately 337 nanometers (nm).

Where the stimulus is a combination of light and oxygen, the reactive compound would therefore be photoreactive with oxygen and preferably operate to change its physical characteristics in response to an interrogating beam of light having a wavelength of approximately 650 nanometers (nm), which is encountered with digital versatile disk (DVD) readers.

Where the environmental stimulus is simply air (more precisely, oxygen), the reactive compound may be one which is operative after an accumulated duration of time to oxidize and alter an optical characteristic thereof. For example, such a reactive compound would change from an optically transparent condition to an optically opaque condition wherein it absorbs light having a wavelength within a desired range. This wavelength could be either 650 nanometers (nm), as discussed above, but may also be in the range of 780 to 820 nanometers (nm). The oxidizing reactive compound may be selected from a group of dyes consisting of methylene blue, brilliant cresyl blue, basic blue 3 and toluidine blue 0.

A methodology of limiting access to data stored on an optical medium such as an optical disk is provided by the first collection of embodiments. Broadly, this methodology comprises the steps of rotating an optical disk in a disk drive at a selected rotational speed, with the optical disk including a substrate layer encoded with information stored thereon as a plurality of readable data structures. A reactive compound is preferably superimposed over at least some of these data structures and this reactive compound operates in an ambient environment containing oxygen to

10

15

20

25

30

35

change optical transmission in response to irradiation for an accumulated duration of time by light having a beam wavelength that is within a selected range. An interrogating beam of light having a beam wavelength that is within the selected range is directed toward the substrate layer and through the reactive compound for the accumulated duration of time.

The step of directing the interrogating beam may be accomplished by directing the beam at the substrate layer for a continuous interval of time that is sufficient to cause the change in optical transmission through the optical medium. Alteratively, the interrogating beam may be directed at the substrate layer for a plurality of discrete intervals of time sufficient to cause such change. Where this is the case, it is contemplated that the interrogating beam may be selectively advanced radially across an outermost surface of the optical disk until the beam interacts with the reactive compound for the plurality of discrete intervals of time. The interrogating beam's wavelength may be approximately 780 nanometers (nm) where a CD-Rom optical disk is utilized, or have a wavelength of approximately 650 nanometers (nm) which is the wavelength employed for digital versatile disks (DVD). Preferably, interrogating beam also has an intensity the approximately 1 milliwatt (mW) of power, which is typically encountered in conventional optical readers.

In a second collection of embodiments of the present invention, a method and apparatus are provided for prohibiting unrestricted duplication of information on an optical medium such as an optical disk, wherein the user manually affects a physical change to the optical disk during an initial use of the optical disk. For example, the user may activate or perform a predetermined procedure for rendering one or more predetermined areas or locations of the optical disk unreadable or more error prone. This

10

15

20

25

30

35

in effect "marks" the optical disk both visually to the user and computationally to a program for accessing information on the optical disk (e.g., graphical data, video data, audio data, text data and/or a software installation program) as having been previously used for accessing the information on the optical disk. Thus, in a subsequent attempt to access the information on the optical disk (e.g., a subsequent attempt to view a multimedia presentation such as a movie, or a subsequent attempt at reinstallation of a software application on the optical disk), it is possible to detect that the information on the optical disk has been previously accessed due to a change in the information on the disk that is able to be read by an optical reader. For example, the optical reader may detect a greater number of read errors than when the optical disk was first accessed for information retrieval.

Alternatively, in other embodiments of the present invention, instead of purposefully creating unreadable portions of the optical disk, a converse method and apparatus may be employed wherein a predetermined portion disk initially unreadable optical is subsequently becomes readable. That is, a mask or covering may be attached to the optical disk during manufacture so that a predetermined portion of information on the optical disk is initially unreadable by an optical reader, but upon initial use of the optical disk, the user physically removes or changes the mask, thereby allowing a sufficient amount of the previously unreadable portion underneath the Accordingly, optical disk accessing mask to be read. software can be performed that detects a state change in the optical disk due to the removing or changing of the mask.

It is a further aspect of at least some embodiments of the present invention that an encoded identifier is provided to a user upon first use of an optical medium of

10

15

20

25

35

Such an encoded identifier is the present invention. particularly useful for prohibiting unwanted duplication and/or use of commercial software since the identifier is derived from a unique physical change of the optical disk, and, for example, serial numbers of the installation Thus, the encoded identifier, when supplied computer. during a reinstallation attempt and decoded, allows the present invention to determine whether the user attempting to install the software on a computer different from the original installation. Thus, upon detecting a state change indicating the software has been previously installed, the present invention may restrict various kinds of access to the information on the optical medium. particular, if the optical disk provides software programs that may be installed on a user's computer, installations beyond the initial installation may be prohibited if the installation is not on the same computer as the initial installation.

Other collections of embodiments of the present invention are also provided hereinbelow. In particular, collections of embodiments are described relating to verification and/or authentication of financial transaction cards or financial transactions.

These and other objects of the present invention will become more readily appreciated and understood from a consideration of the following detailed description of the exemplary embodiments of the present invention when taken together with the accompanying drawings, in which:

#### BRIEF DESCRIPTION OF DRAWINGS

Fig. 1 is a perspective view of an optical readout system utilizing an optical disk (shown in partial phantom) according to the present invention;

Fig. 2 is a side view in elevation, and in partial cross-section, showing the optical readout system's interrogating beam positioned beneath a first type of data

10

15

20

25

30

35

structure stored on an optical disk according to a first exemplary embodiment of the present invention;

Fig. 3A is an enlarged cross-sectional view of area "A" in Fig. 2;

Fig. 3B is an enlarged cross-sectional view of area "A" in Fig. 2 after an accumulated duration of time so that the reactive compound associated with the optical disk of the first exemplary embodiment of the present invention has undergone a change in its physical characteristics;

Fig. 4 is a side view in elevation, and in partial cross-section, showing the optical readout system's interrogating beam positioned beneath a second type of data structure stored on the optical disk according to the first exemplary embodiment of the present invention;

Fig. 5A is an enlarged cross-sectional view of area "A'" in Fig. 4;

Fig. 5B is an enlarged cross-sectional view of area "A'" in Fig. 4 after an accumulated duration of time so that the reactive compound associated with the optical disk of the first exemplary embodiment of the present invention has undergone a change in its physical characteristics;

Fig. 6A is an enlarged cross-sectional view of an area "Bl" of an optical disk according to a second exemplary embodiment of the present invention, with the optical readout system's interrogating beam positioned beneath a first type of data structure stored thereon;

Fig. 6B is an enlarged cross-sectional view of the same area "B" after an accumulated duration of time so that the reactive compound associated with the optical disk according to the second exemplary embodiment of the present invention has undergone a change in its physical characteristics;

Figure 7A is an enlarged cross-sectional view of an area "B'" of an optical disk according to a second exemplary embodiment of the present invention, with the

10

15

20

25

35

optical readout system's interrogating beam positioned beneath a second type of data structure stored thereon;

Fig. 7B is an enlarged cross-sectional view of the same area "B'" after an accumulated duration of time so that the reactive compound associated with the optical disk according to the second exemplary embodiment of the present invention has undergone a change in its physical characteristics;

Fig. 8 is a perspective view, partially pealed away, of a package for containing an optical disk utilizing any one of a variety of reactive compounds according to the present invention; Figure 9 is a bottom plan view showing a variety of applications for the reactive compound associated with an optical disk according to the present invention;

Figs. 10A, 10B and 10C present a flowchart of the steps performed when the present invention is used to install computer software residing on an optical disk that conforms with the inventive aspects of the present invention, wherein the user is required to make a manual change to the optical disk during the first installation using the optical disk;

Figs. 11A and 11B illustrate a manual approach to irreversibly changing the physical characteristics of an optical disk manufactured according to the present invention. That is, the optical disk here includes an additional layer bonded to the optical disk wherein upon removal by the user, the information encoded on the optical adjacent to the additional layer is damaged;

Fig. 12 illustrates the removal of the additional layer (denoted a "ripcord") that is also shown in Figs. 11A and 11B;

Figs. 13A and 13B illustrate an alternative embodiment to the optical disk embodiment of Figs. 11A - 12B for purposefully damaging an optical disk manufactured

10

15

20

25

30

35

according to the present invention. In particular, in Figs. 13A and 13B, a chemical container or sack is bonded to an optical disk so that upon rupturing of the container (during, e.g., an initial optical disk use), the information on the optical disk is purposefully damaged, thereby allowing a subsequent installation process to detect the previous access to the information on the optical disk;

Figs. 14A and 14B illustrates cross-sections of the optical disk of Figs. 13A and 13B, wherein Fig. 14A shows the chemical container prior to rupturing and Fig. 14B shows the chemical container after rupturing;

Figs. 15A and 15B illustrate another alternative embodiment for purposefully damaging an optical disk wherein an external device is used that can etch or scar the optical disk and thereby reduce the readability of disk information in a particular area of the disk;

Figs. 16A and 16B illustrate yet another embodiment of the present invention for purposefully damaging an optical disk manufactured according to the present invention. In the embodiment of these figures, an external device is used for applying one or more chemicals to a particular or predetermined portion of the optical disk and thereby inducing additional read errors from an optical disk reader;

Figs. 17A and 17B illustrate an alternative embodiment of an optical disk manufactured according to the present invention, wherein an additional layer is provided on the optical disk during manufacture for hiding or masking a particular portion of the information on the optical disk;

Fig. 18 illustrates the removal of the additional layer (also denoted a "ripcord") from the optical disk of Figs. 17, wherein the optical disk information masked by the ripcord is now capable of being read by an optical reader;

15

20

25

30

35

Figs. 19A and 19B illustrate another embodiment of the present invention, wherein a container or sack having one or more chemicals is attached to an optical disk during manufacture so that this container initially masks or distorts information encoded into the optical disk; however, upon rupturing of the container, the masked information on the optical disk is now capable of being read by an optical reader;

Fig. 20 illustrates the embodiment of the present invention shown in Figs. 19A and 19B, wherein Fig. 20 shows the cross-section of the optical disk after the chemical container is ruptured; and

Figs. 21A and 21B illustrate the use of an external device having an enclosed chemical that can be used for removing or changing the optical characteristics of a patch or additional layer that masks information on the optical disk;

Fig. 22 is a flowchart of the steps performed in the present invention in verifying the identity of user requesting to perform an electronic financial transaction via, for example, the Internet.

#### DETAILED DESCRIPTION

The present invention is, in one sense directed to an optical disk for use in a computer's optical readout system, which optical disk is constructed to prohibit unrestricted access, by the readout system, to information stored on the disk. As such, the optical disk of the present invention is particularly adapted as an alternative approach for combating the growing piracy problems resulting from the illegal misappropriation of software products. As will be appreciated, the present invention is also directed to a methodology for limiting access to data stored on an optical medium. While both the optical disk of the present invention and the methodology for utilizing

10

15

20

25

30

35

the same in a computer's optical readout system is described herein with reference to a conventional CD ROM disk, the ordinarily skilled artisan would readily appreciate that the teachings of the present invention may also be applied to other types of optical disks, such as audio CD's, WORM (Write Once Read Many) optical disks, and DVD (Digital Versatile Disks), to name only a few.

With this in mind, then, a typical optical readout system 10 of a computer incorporating an optical disk according to the first exemplary embodiment of the present invention is introduced in Figs.1 and 2. Optical readout system 10 broadly includes a disk drive 12 which is operative to rotate an optical disk 50 at a selected rotational speed, a light source 20 for producing an interrogating beam of light and a detector 40 which is operative to collect a returned component of the interrogating beam and to produce an output signal correlated to this returned component.

More specifically, and as is known in the art, disk drive 12 includes a motor 14 comprising a drive shaft 16 and a spindle 18 to which the CD-Rom optical disk 50 is mounted, and this motor 14 operates to constantly vary the rate at which the optical disk 50 is spun so that, regardless of where detector 40 is located in relation to the radius of optical disk 50, the portion of disk 50 located immediately above detector 40 is always moving at the same rate. Unlike conventional magnetic disks, which are divided radially into sectors and spin at a constant angular velocity, data on a CD-Rom disk is contained in a single track that spirals from the center of the disk to This track is still divided into its circumference. sectors, but each sector is the same physical size. Using a method known as constant linear velocity, the disk drive 12 constantly varies the rate at which (optical disk) 50 spins so that as detector 40 moves toward the center of the

10

15

20

25

30

35

optical disk 50 the disk increases its rotational speed. The effect of this is that the optical disk 50 can contain more sectors than a conventional magnetic disk and, consequently, more data.

Light source 20 generates an incident or interrogating beam of light via laser diode 22 and this beam 23 is initially collimated by collimator 26. The collimated beam is then directed toward a polarized beam splitter, or prism 28, after which it is sent through a quarter wave plate 30. Alternatively, for optical readout systems wherein the laser diode 22 and collimator 26 are offset in position relative to beam splitter 28, a wedge mirror prism may be employed to direct the beam in an axial direction relative to optical disk 50. After collimated beam 24 encounters quarter wave plate 30 it is thereafter directed through an objective lens 32 and an appropriate focusing coil to produce a concentrated and focused interrogating beam 25.

Focused interrogating beam 25 penetrates substrate 52 of optical disk 50 and typically strikes a metallic reflective layer 56 that is coated on the substrate 52. Metallic layer 56, itself, is encoded with information stored as a plurality of data structures 58 and is specifically contoured to include a sequence of lands 57 and pits 59 which define these data structures 58. may be accomplished with a conventional stamping process wherein metallic layer 56 is pressed into substrate 52 to create pits 59. Lands 57 are those areas which are not pressed and remain in their original position. Metallic layer 56 is approximately 1 micron thick and pits 59 are, by design, only one quarter wavelength of the wavelength of interrogating beam 25. Lands 57 and pits 59 correspond to the l's and O's used to store data information. interrogating beam 25 from laser diode 22 is focused at the surface level of lands 57, as shown. Whereas, light that strikes a pit 59 is scattered, light that strikes a land 57

15

20

25

30

is reflected as a returned beam 27 and directed back through polarized beam splitter 28. Beam splitter 28 deflects the returned beam 27 towards a tracking error detector 42, which controls tracking and focusing of the laser beam to sub-micron levels, and ultimately to light detecting photo diode 44. Light that strikes photo diode 44 generates a small electrical voltage at electrical leads 46, 48 and these voltages are matched against a timing circuit to generate the stream of 1's and 0's that the computer can understand. Accordingly, photo diode 44 converts the presence or absence of lands into an electrical signal.

The construction of a first exemplary embodiment of optical disk 50 may better be appreciated now with reference to Fig. 3(a) which is an exploded view of area "A" in Fig. 2. Optical disk 50 is constructed somewhat similarly to CD-Rom disks or audio compact disks now available. That is, as discussed above, optical disk 50 includes a substrate 52 and a metallic layer 56 upon which a protective coating 54 is placed. The metallic layer 56 is formed so that it is encoded with the information stored thereon as the plurality of data structures 58 that are readable by interrogating beam 25. Substrate layer 52, which may be formed out of polycarbonate, is disposed in a confronting relationship with metallic layer 56. As shown, metallic layer 56 is interposed between a lower surface 55 of protective coating 54 and substrate 52.

Unique to the present embodiments of the invention, though, is the inclusion of a film of reactive compound 60 that is superimposed over at least some of data structures 58. This reactive compound 60 is selected to be of a type which is operative to change physical characteristics in response to a selected stimulus, and thereby to affect readability of the information by interrogating beam 25.

10

15

20

25

30

In this first exemplary embodiment of optical disk 50, reactive compound 60 is formed as a coating on a lower surface 51 of substrate 52. In alterative embodiments, the reactive compound may be:

- (a) interposed between the metallic layer 56 and the inner surface of substrate 52 as discussed more thoroughly below with reference to Figs. 7A-7D, or
- (b) embedded within the substrate 52. The selected environmental stimulus to which the reactive compound responds, regardless of its location in the optical disk, will also be discussed more thoroughly below with reference to certain classes of chemical materials from which the reactive compound may be chosen. Briefly, however, for each environmental stimulus to which the reactive compound responds, the reactive compound changes its optical transmission characteristics from an optically transparent condition to an optically opaque condition whereby it masks the data structures and affects the integrity of the electrical signal generated by the computer's optical readout system.

For example, Figs. 3A and 3B illustrate how the integrity of the optical readout system's electrical signal is affected when the interrogating beam 25 encounters a land 57. As shown in Fig. 3A, interrogating beam 25 initially is able to penetrate both the reactive compound 60 and substrate 52 to detect the presence of land 57, which for purposes of discussion only, may correspond to data information in the form of the binary 1. Accordingly, interrogating beam 25 is reflected off of metallic (reflective) layer 56 as a returned beam 27 which is thereafter detected by light detecting photo diode 44, resulting in the generation an electrical signal correlated to land 57.

However, and as may now be seen with reference to Fig. 35 3B, after an accumulated duration of time, a region 62 of

15

20

25

30

35

reactive compound 60 changes its physical characteristics to an optically opaque condition whereby interrogating beam 25 is absorbed by the reactive compound 60 and is no longer able to penetrate the substrate 52 to detect the presence of land 57. Therefore, light detecting photo diode 44 does not receive a returned beam, as expected, and generates an improper electrical signal to the computer. As far as the optical readout system 10 is concerned, the interrogating beam 25 is positioned directly beneath a pit as opposed to a land, resulting in an incorrect data transferred to the computer.

Figs. 4 and 5A-5B illustrate the situation where interrogating beam 25 is positioned directly beneath a data structure 58 in the form of a land 57. It may be appreciated that, here, light source 20 has been advanced either radially or circumferentially across the outer surface 51 of substrate 52 to a different location as dictated by the computer's program. Looking at the exploded area A' in Fig. 5A, it is seen that interrogating beam 25 is initially able to penetrate both reactive compound 60 and substrate 52 and impinge upon metallic layer 56 which coats land 57. Because reflective material 56 in this region is not positioned at the level of the interrogating beam's focal point, interrogating beam 25 is Thus, either no returned beam is reflected or scattered. an insufficient amount of light is reflected back to photo diode 44, thereby resulting in the generation of a binary electrical signal by detector 40 which corresponds to the presence of the encountered pit 59. This is the expected result.

After an accumulated duration of time, the region 62 of reactive compound 60 which is exposed to interrogating beam 25 becomes darkened or opaque. Light in this region 62 is absorbed and not allowed to penetrate substrate 52 to detect the presence or absence of pit 59.

10

15

20

25

30

35

The result is, therefore, the same in that detector 40 generates a binary electrical signal, such as a zero, corresponding to the presence of a pit.

A second exemplary embodiment for the optical disk according to the first collection of embodiments may now be appreciated with reference to Figs. 6A - 6B and 7A - 7B. Here, the reactive compound 160 of optical disk 150 is shown to be interposed between the substrate 152 and metallic layer 156. While it is inherently more difficult to manufacture optical disk 150 than it would be to manufacture optical disk 50 which is referenced in the first exemplary embodiment of the present invention, the construction of optical disk 150 may be preferred from a performance standpoint because reactive compound 160 is located in a region where interrogating beam 125 would have a greater beam intensity than would beam 25 due to its relatively reduced focal width in this region. practical purposes, however, the results would nonetheless be the same.

For example, Fig. 6A again illustrates the situation where interrogating beam 125 is positioned beneath a land 157 such that the beam is reflected off of metallic layer 156 as a returned beam 127 which would be recognized by the detector and correctly converted into a corresponding binary electrical signal. In Fig. 6B, on the other hand, it is shown that after an accumulated duration of time, the region 162 of reactive compound 160 which has been exposed to a given environmental stimulus changes its physical characteristics from an optically transparent condition to an optically opaque or darkened condition. interrogating beam 125 is absorbed in region 162 and no returned beam is detected, resulting in the generation of a binary electrical signal by the computer's optical readout system, despite the presence of pit 159. In Figs. 7A - 7B the situation is similar to that discussed above

15

20

25

30

35

with reference to Figs.5A - 5B. Thus, when interrogating beam 125 is positioned directly beneath a pit 159, the computer's optical readout system would generate the proper binary electrical signal irrespective of the physical characteristic of reactive compound 160 in region 162.

#### A. Classes of Materials For the Reactive Compound

Various classes of materials have been found which exhibit appropriate physical characteristics for utilization in the optical disk according to the exemplary embodiments of the present invention. Each of these materials responds to either a specific environmental condition, or a combination of environmental conditions, to mask the data structures on an optical disk, thereby affecting their readability by the computer's optical readout system.

#### 1. Photo Reactive Compounds

It has been found that photoreactive materials exhibit desired light absorption characteristics and that these materials may be formed as a coating on an optical disk to mask at least some of the disk's data structures from detection by an optical readout system. Photochromes, and specifically the spiropyran class of photochromes, have Photochromism is the phenomenon particular utility. whereby the absorption spectrum of a molecule changes reversibly or irreversibly when the sample is irradiated by light having certain wavelengths. For example, a colorless compound can change to a quasi-stable colored structure when it is irradiated with infrared light. While a specific photochromic or photosensitive material of the spiropyran class is discussed herein for use in the present invention, the ordinarily skilled artisan would appreciate that other photochromic materials such as aziridine derivatives, diohydropyrene derivatives, bipyradine derivatives, fulgide derivatives, thioindigo derivatives, azobenzene derivatives, salicylideneaniline derivatives,

xanthane derivatives, oxazine derivatives may also prove useful.

spiropyran class dye, having the chemical composition 6-nitro-1'3'3'-trimethylspiro-[2H-1benzothiopyran-2,2'-indoline], or 6-nitro-1-5-BIPS for 5 short, is discussed in Tarkka, Richard U. Talbot, Marc E., "Holographic storage in a near-ir sensitive photochromic dye." Optic Comm. 109, 54-58 (1994), the teachings of which are incorporated herein by reference. When exposed to infrared light having a wavelength of 10 approximately 780 nanometers (nm), a wavelength which is predominantly utilized in current optical readout systems, this dye becomes colored. The dye may thereafter be returned to its optically transparent state upon exposure to an ultraviolet source at approximately 337 nanometers 15 This ability to erase the color from the dye is not fatal in that it requires a relatively expensive and difficult to find light source. 6-nitro-1-S-BIPS is preferably applied as a coating to the substrate of an optical disk as illustrated in Figs. 3 - 5 above. With 20 derivative, other spiropyran or chromophores, it is recognized that the environmental is simply exposure to the light sources stimulus interrogating beam.

25 2. Compounds Which are Photoreactive in the Presence of Oxygen

Two materials which may also be used in conjunction with the optical disk according to the present invention are photoreactive in the presence of an ambient environment containing oxygen.


#### a. Compound I

30

One such material is denoted as compound I below:

10

15



COMPOUND 1

Compound 1 is made by treating tetramethylindolium iodide with 10 Molar equivalents of 1N sodium hydroxide in water with good mixing. As compound I is formed, it is extracted into the hexane co-solvent according to the following reaction:

Tetramethylindolium iodide

COMPOUND 1

Alternatively, one molar equivalent of triethylamine in dichloromethane can be used and the product can be isolated by extraction with water, evaporation of a solvent and The aqueous base method is dissolution in hexane. preferred in that it yields in excess of 80% of the desired final product.

Compound I is photoreactive with oxygen and sensitive to ambient florescent light over several (> 18 hrs) exposure, is quickly (< -10 mins) photo oxidized upon exposure to an incandescent 150W lamp at a distance of 12 Compound I also reacts upon exposure to light inches.

# SUBSTITUTE SHEET (RULE 20)

10

15

20

25

26

having a wavelength of approximately 650 nanometers (nm) and an intensity approximating that of a digital versatile disk (DVD) player light source. Accordingly, compound I is useful for application to an optical disk incorporated in developed DVD drives.

#### b. Compound II

Another material which is photoreactive in the presence of oxygen can be made from quinoline salts and related enamine derivatives. This photoreactive material is denoted as compound II below and may be prepared, similarly to compound I, according to the following reaction:

With both compounds I and II above, it should be appreciated that the environmental stimulus which causes them to change in optical transmission is a combination of both light and oxygen. Moreover, these compounds are specifically adapted for use in a computer's optical readout system which utilizes a light source having a wavelength of 650 nanometers (nm). Because these compounds react to change their light absorption characteristics in the presence of an ambient environment containing oxygen, the required amount of time for such change varies depending upon the wavelength of the ambient light. It is, therefore, desirable that the optical disks coated with either compounds I or II, be packaged in an inert

### SUBSTITUTE SHEET (RULE 26)

environment and/or a standard hermetic packaging. To this end, Fig. 8 shows that such an optical disk 250 is preferably contained in a package 210 in the form of an aluminum bag coated with polyethylene. Contained within package 210 is an inert gaseous environment, such as argon, nitrogen, neon, helium, or other ambient gas.

#### c. Materials Which Are Oxygen Reactive

It has also been found that certain oxygen reactive materials may be used in an optical readout system having a light source at a selected wavelength. One class of such materials is based upon the reduced forms of the well known dye, methylene blue. The method of synthesis and the oxygen dependent reoxidation to form the colored form of the methylene blue dye is shown below:

15

10

5

20

Various reducing agents can be used to reduce methylene blue and its many derivatives, with zinc and acetic acid being one possibility. The color of methylene blue when reduced is pale yellow and it quickly is re-oxidized to be dark blue by oxygen in air. The rate of this reaction is somewhat dependent on the medium, however. In polyurethane films, this rate has varied from about 10 minutes to 30 minutes depending on the concentration. When sodium borohydride residue is not quenched in these films, they gradually turn from clear to blue over several hours. The

# SUBSTITUTE SHEET (RULE 26)

blue form of the methylene blue dye absorbs strongly at 650 nanometers (nm), the centered wavelength for DVD laser light readers.

Other dyes which are reactive in the air (e.g., to oxygen) perform similarly to the methylene blue and have maximum absorbencies that can vary by several tens of nanometers. The structures of some of these dyes known to perform like methylene blue and their commercial names are shown below:

10

5

15

20

toluidine blue 0

25 Finally, for optical readouts systems employing an interrogating beam having a wavelength of 780 nanometers (nm), a wavelength which is predominantly used in CD-Rom readers, one dye has been shown to reoxidize over approximately 48 hours and thereafter absorb light at this wavelength. The synthesis and oxidation of this dye, denoted as compound III, is shown below:

It is certainly contemplated that numerous other similar dyes can be synthesized to operate effectively in a given optical readout system. With each of the air reactive materials discussed herein, as with those materials discussed above which are photoreactive in an ambient environment containing oxygen, it is desirable to package the optical disk containing the dye in an inert environment as shown in Fig. 8.

10

15

20

5

With an understanding of the various compounds which the reactive compound of the present invention may assume, the ordinarily skilled artisan in this field would readily appreciate that the particular compound selected would depend on a variety of parameters of the operating environment. Where a CD ROM application is preferred, the reactive compound would necessarily be one that is compatible with this environment, sensitive to the infrared lasers used in the CD-Rom's optical readout system (i.e. 650 nm or 780 - 830 nm) and will react to the lower powered intensity of the interrogating beam (approximately .15 to For those reactive compounds which are .6 mW of power. reactive in the presence of oxygen, a user would of course be careful to avoid exposure of the optical disk to an ambient environment containing either oxygen, or light and

# SUBSTITUTE SHEET (RULE 26)

10

15

20

25

30

35

oxygen, in order to prolong the useful life of the optical disk.

A primary thrust of the present invention is, of course, to deny access to a specially coated optical disk, and preferably a CD-Rom disk, beyond one or more authorized To this end, one potential use for coating an optical disk with a reactive compound would be to allow for sample disks to be given away to customers in order for them to determine whether or not the product is worth Once the product has been evaluated, the purchasing. customer then might be required to return the product to the vendor and buy a commercial version of the sample In one novel application of the present optical disk. invention, such specially coated optical disks may have music encoded on them so that such disks are only playable for a particular period of time and/or for a particular number of times. Thus, optical disks that automatically expire are provided by the present invention. Moreover, note that movies and other multimedia presentations can be commercially provided in a similar fashion. Alternatively, a customer could purchase a coated optical disk and load it onto a computer's hard drive prior to the reactive compound changing its physical characteristics and rendering the optical disk unreadable.

Another potential application is the rental of optical disks which contain the reactive compound. Such an optical disk may be rented, much like videos cassette at a low cost and played until such time as the optical readout system of the disk player is no longer able to detect the presence or absence of the encoded information.

As shown in Fig. 9, the reactive compound may be applied to the optical disk in a variety of patterns. Fig. 9, of course, only illustrates a few such applications and others are certainly contemplated without departing from the concepts of the present invention. To illustrate,

10

15

20

25

30

35

reactive compound 260 may be embossed as a film over an entire sector of optical disk 250, such as representative sectors 252 and 254. Alteratively, the reactive compound 260 may be applied to only a portion of a sector, such as region 256 in Fig. 9. Although, the entire surface of optical disk 250 could be coated with reactive compound 260, this is not a necessity, because the compound could merely be applied to that portion of the disk which contains critical information for the optical readout system to access in order for the software product to With specific reference to the function properly. spiropyran class of photochromes discussed above, it is also anticipated that a reactive compound of this type, which is adapted to reversibly change between a darkened colored state and a transparent state, could be initially be applied in its darkened state to the surface of the A software application residing on an optical disk. optical disk for the present invention may execute properly only in the event that the optical readout system continues to process information as if no data were contained in this region. Once the photochrome changes to the transparent condition upon sufficient exposure to light, the optical readout system would be able to detect the plurality of and the software application then data structures, discontinues its proper function.

With the foregoing in mind, the first collection of embodiments of the present invention is directed to an article of manufacturer adapted to be encoded with data and further adapted so that duplication of the data by an optical scanning machine may be restricted. To this end, the article of manufacturer comprises a substrate fabrication from a selected material and having a substrate surface which contains the data. A reactive compound is formed as a coating on at least a portion of the substrate surface and this reactive compound is operative to change

10

15

20

25

30

35

from an optically transparent state to an optically opaque state in response to a irradiation for an accumulated duration of time by light having selected characteristics, thereby to prevent the light from the optical scanning machine from penetrating the reactive compound and to render the data undetectable by the machine.

It should also be appreciated from the foregoing that another aspect of the present invention is a methodology of limiting access to data stored in an optical medium according to the first collection of embodiments. Broadly, this methodology comprises the steps of rotating an optical disk in a disk drive at a selected rotational speed, with the optical disk including a substrate and a metallic layer encoded with information stored thereon as a plurality of readable data structures and including a reactive compound superimposed over at least some of these data structures. compound is operative in an ambient reactive optical to change environment containing oxygen transmission in response to irradiation for an accumulated duration of time by light having a beam wavelength that is The broad methodology would also within a selected range. include a step of directing an interrogating beam of light having a beam wavelength that is within the selected range toward the substrate and through the reactive compound for the accumulated duration of time.

The step of directing the interrogating beam of light could be accomplished by directing the beam toward the substrate for a continuous interval of time that is sufficient to cause the change in optical transmission. The methodology also contemplates that the interrogating beam can be directed at the substrate for a plurality of discrete intervals of time sufficient to cause the change in optical transmission. This might occur, for example, where the light source of the computer's optical readout system selectively advances the interrogating beam radially

10

15

20

25

30

35

across an outermost surface of the optical disk until the beam interacts with the reactive compound for the plurality of discrete intervals of time. It is preferred that the methodology be practiced with a beam wavelength approximately either 780 or 650 nanometers (nm) and a beam intensity of approximately 0.14 milliwatts (mW) 0.6 mW of power.

In Figs. 10A, 10B and 10C, a representative flowchart is provided of the steps performed in the method of the present invention according to the second collection of the summary described in embodiments as That is, the flowchart of these figures hereinabove. illustrates the steps performed to prohibit unrestricted duplication and/or access of information on an optical medium or disk manufactured according to an embodiment of the present invention. In particular, the present method provides for purposefully inducing a physical change to the optical disk during its use; i.e., the physical change may be caused substantially automatically by, the the optical disk, software on activation of alternatively may be caused as a purposeful effect of manual action by the user. More particularly, the flowchart of Figs. 10 illustrates the steps performed when installing software on a user's computer from an optical disk configured according to the present invention. in step 1000, the user inserts the optical disk into the optical disk drive (also denoted optical readout system or optical reader hereinabove). Subsequently, in step 1004, the user initiates or activates a start-up or installation program for processing information on the optical disk during an installation of the software on the optical disk. Note that this installation program may be read from the optical disk as a first portion of the information read. Alternatively, this installation program may be downloaded Upon activating the installation from the Internet.

10

15

20

25

30

35

program, the user may be allowed the option of either activating a demonstration version of the optical disk software wherein a manual change to the optical disk is not Assuming such an option is available, in step 1008, a response from the user is solicited as to whether the user desires to use a demonstration version of the example, prior to performing a for software, installation on the user's computer. Accordingly, assuming the user requests to use a demonstration version, steps 1012 through 1020 are performed, wherein a demonstration version of the software may be loaded onto the user's computer thereby allowing the user to perform, for example, a restricted set of features of the optical disk software application.

Alternatively, if in step 1008, the user desires to fully install the software application from the optical disk, then step 1024 is performed, wherein one or more decryption procedures are installed into the user's computer from, e.g., the optical disk or the Internet. Note that at least some of the information residing on the optical disk is encrypted so that it is not easily duplicated as a non-executable sequence of bits or characters, and subsequently reverse engineered to obtain a fully functioning executable version of the software on the optical disk. Thus, it is to be understood that in the subsequent steps for installing the application software from the optical disk to the user's computer, that the encryption procedures installed in this step (1024) are activated one or more times for decrypting at least some crucial information transferred between the optical disk and the user's computer.

Subsequently, in step 1028, a determination is made as to whether a predetermined area of the optical disk has an occurrence of a profile of an expected physical change to the optical disk. That is, the start-up program assumes

10

15

20

25

30

35

that the optical disk is in a particular predetermined physical configuration or state when obtained from the manufacturing process, and during this step, the start-up program determines if the physical characteristics of the optical disk conform to this assumed initial state or whether an occurrence of a particular profile of an expected physical change has occurred. In particular, note that the expected physical change, if detected, is assumed to be due to a previous installation of the software of the optical disk.

It is worth mentioning that such an expected physical change during such a software installation procedure may be due to any one of a number of user initiated techniques. For example, an additional layer or substance can be incorporated into the optical disk in a predetermined area so that upon purposeful removal by the user of the layer or substance (either mechanically or chemically), the optical information coinciding on the optical disk with this layer is changed in an expected arrangement so that in a subsequent installation attempt, this expected arrangement In particular, examples of such can be detected. techniques are discussed hereinbelow and illustrated in Alternatively, in 11A through 14B. technique, an external device may be utilized by the user to intentionally change a predetermined portion of the optical disk as described hereinbelow with reference to In yet another technique, a Figs. 15A through 16B. predetermined portion of the optical disk can be initially provided with an additional coating or layer that distorts or hides a predetermined portion of the optical disk information so that upon first use of the optical disk for installing the software therein, this layer is either removed or changed in some fashion so that the information encoded underneath is capable of being read by the optical disk reader. In particular, this technique is described

10

15

20

25

30

35

and illustrated hereinbelow with reference to Figs. 17A through 21B. However, for each such technique it is an aspect of the present invention that in most embodiments the predetermined portion of the optical disk having an intentional change is limited to a minority of the storage capacity of the optical disk.

in one important class of embodiments Moreover, wherein the expected physical change is due to a change in the errors detected (e.g. either an increase or a decrease in errors), additional steps may be performed by software implementing the flowchart of Figs. 10 wherein these additional steps activate and deactivate the optical disk error correction module(s) of the user's computer system. Note that this becomes an important time saving aspect of the present invention in that considerable time can be consumed by the error correction module(s) in attempting to read purposefully induced unreadable errors. deactivating the error correction module(s) just before a determination of whether an occurrence of an expected profile of errors is made (i.e., just before steps 1028 and 1052 of Figs. 10), and subsequently reactivating the error correction module(s) immediately thereafter, considerable time may be saved in, for example, (re)installing software from the optical disk, activating a presentation of a movie from the optical disk, etc.

Returning now to the steps of the flowchart of Figs. 10, assuming that in step 1028 the expected change from the original optical characteristics of the optical disk is not detected, then step 1032 is performed wherein the installation procedure may request user specific data such as the user's name and/or other user identifying information. Following this step, in step 1036, the installation procedure may install substantially all the software from the optical disk with the exception of one or more portions that are necessary for activating the

10

15

20

25

30

35

software. Subsequently, in step 1040, the installation process sets internal flags indicating that an initial full installation of the software is in progress. This step provides a substantially failsafe feature of the present invention so that if there is a computer failure during installation, these internal flags can be subsequently detected in the persistent storage (e.g., the hard disk) of the user's computer, and subsequently used to reinitiate the installation procedure. Subsequently, in step 1044, the user is instructed to remove the optical disk from the computer and physically modify the optical disk in a predetermined manner and subsequently reinsert the optical disk into the computer.

Assuming that the optical disk has been reinserted, in step 1052 the installation procedure determines whether an expected profile of a physical change to the optical disk has occurred in a predetermined area of the disk. particular, various embodiments of the present invention determine the physical change in the optical disk by analyzing a change, for example, in the errors generated when attempting to read certain predetermined locations on the optical disk. For instance, the change may be detected (a) a total number of errors generated in a sampling of locations in an area of the optical disk (e.g., a detected number of errors greater than a minimum threshold, or less than a maximum threshold), (b) a density of errors generated in a sampling of locations in an area of the optical disk (e.g., a detected density of errors greater than a minimum threshold or less than a maximum threshold), (c) a relative number of errors generated in a sampling of locations in an area of the optical disk, (d) a pattern of errors generated in a sampling of locations in an area of the optical disk, (e) a statistical analysis of the errors in a sampling of locations generated in an area of the optical disk, (e.g., a regression analysis). Moreover,

10

15

20

25

30

35

instead of determining various measurements related to errors detected, the physical change in the optical disk may be detected by computing a measurement related to the non-error generating locations of an area of the optical Thus, by replacing the word, "errors", with the word, "non-errors" in (a) through (e) above, additional examples for detecting a change to the optical disk are obtained. Further, note that the change may be detected stochastically wherein, for example, a probability or likelihood measurement is computed for determining whether a change has been detected. Note that the physical change may be removing, replacing or rearranging an entire wedge extending through all layers of the optical disk. instance, a tab on an edge on an optical disk may be broken from the optical disk as part of an initial installation. Moreover, in some embodiments, such errors are not only detectable, but they are also not capable of being corrected by error correction circuitry since the errors are so prevalent. However, it is also within the scope of the present invention to detect such a change by other techniques than error detection. For example, a detachable optically readable layer may mask alternative optically (and/or Thus, by removing information. readable rearranging) the detachable optically readable layer and exposing the alternative data, a change to the optical disk can be detected.

Referring again to step 1052 of Fig. 10C, if an expected profile of the requested physical change to the optical disk has not occurred, then the installation procedure terminates (i.e., the "no" branch is taken). However, assuming that such a profile of an expected physical change is detected, step 1056 is performed wherein the installation process determines a collection of characteristics that uniquely identify the computer and the optical disk combination. For example, characteristics

10

15

20

relating to the user's computer may be various serial numbers associated with the central processing unit, and Additionally, other peripheral processors or devices. disk characteristics, the optical regarding installation software samples the detected changes to the optical disk in the predetermined area and subsequently encodes the locations of the changes in this predetermined area by generating one or more codes related to the optical readability of the disk in the predetermined area. by combining the characteristics of the user's computer with the encoded characteristics of the physical change to the optical disk and possibly an encoding of the user data entered, a unique encoded identifier can be generated as, e.g., a character string as described in step 1060. Note that hereinafter the unique identifier will be denoted as a "configuration fingerprint." As an aside, note that it is important that the unique physical characteristics of the optical disk be encoded into the configuration fingerprint since otherwise there is the potential for a user to use a configuration fingerprint based solely on the characteristics of the user's computer to install software from optical disks of the present invention on any number of computers.

In step 1064, the configuration fingerprint is written into persistent storage on the user's computer, 25 additionally, the configuration fingerprint is output to Subsequently, in step 1068, the installation procedure instructs the user to remove the optical disk from the computer and manually write the configuration fingerprint on the optical disk. Additionally, 30 described in step 1072, the user is instructed to enter the configuration fingerprint as written on the optical disk as input into the user's computer. Note that the entering of the configuration fingerprint by the user and the subsequent checking to determine whether the computed 35

15

20

25

30

35

configuration fingerprint and the one entered by the user are identical provides a level of assurance that the configuration fingerprint written on the optical disk is identical to the computed configuration fingerprint. during subsequent important since а assurance is optical reinstallation attempt from the disk, the configuration fingerprint is recomputed and a match with a user input fingerprint is required before the software will be (re)installed on the user's computer.

10 Assuming that eventually the configuration fingerprints match in step 1076, step 1080 is performed wherein the installation procedure completes installation of the software from the optical disk.

Returning now to step 1028, if the installation procedure determines that in a predetermined area of the optical disk, there is indeed an occurrence of a profile of original optical from the expected change an characteristics of the optical disk as manufactured, then the configuration 1084 is performed wherein step fingerprint for the optical disk is computed as in the steps 1056 and 1060. Following this step, in step 1088, is instructed to enter the configuration the user fingerprint written on the optical disk. Thus, in step 1092, the installation procedure determines whether the computed configuration fingerprint matches the input fingerprint provided bv the configuration Accordingly, if these two fingerprints do not match, then the installation procedure quits without fully installing the software. Alternatively, if the fingerprints, match, then the remaining portion of the installation completed.

It is worth noting, however, that even though the software of the optical disk may not be able to be installed at a computer different from the initial installation computer, it is an aspect of the present

15

20

25

30

35

invention that the software may be executed directly from the optical disk in the case where the software cannot be installed due to, for example, a mismatch of configuration fingerprints as determined in step 1092 above. That is, it is an aspect of the present method that the user may be able to execute the software of the optical disk on any computer capable of reading the disk by executing the software directly from the disk.

In some embodiments of the present invention, the configuration fingerprints may not be required to exactly match in order for a complete reinstallation (step 1096 above) to be performed. In particular, it is an aspect of these embodiments of the present invention that as long as the configuration fingerprints are sufficiently similar, the installation process of step 1096 is performed. Thus, if the optical disk becomes scratched accidentally in the predetermined area where the expected change is to occur, and certain components of the user's computer were replaced, then the user may still be allowed to install the software on the optical disk due to a sufficient similarity between the computed configuration fingerprint and the input configuration fingerprint.

Referring now to Figs. 11A - 21B, a second collection of embodiments (denoted hereinafter as the "manually activated embodiments") of the present invention are illustrated. Accordingly, these embodiments, as with the previous embodiments described, prohibit unrestricted duplication of information on an optical disk manufactured according to the present invention. However, in the manually activated embodiments, the user manually effects a physical change to the optical disk during an initial use so that this change can be detected upon subsequent uses of the optical disk. Thus, as with the previous embodiments that automatically change optical states when irradiated by an optical scanning machine, there is protection against

10

15

20

25

30

copying, duplication, unauthorized installation or use of the data on the optical disk.

In Figs. 11A - 12, a first of the manually activated embodiments is illustrated. In the embodiment illustrated in these figures optical disk 1150 includes painted surface 1154 and protective lacquer layer 1158 as the uppermost surfaces. Additionally, as is typical for such disks, there is also a metalized or reflective layer 1162 and a transparent polycarbonate layer 1166. To these layers the present invention provides an extra or additional assembly 1170 for purposefully generating an expected profile of read errors on the optical disk 1150 (this additional assembly 1170 is hereinafter also denoted as a "ripcord") when this assembly is, for example, mechanically removed.

In the present embodiment, the ripcord 1170 includes (a) a substantially tear resistant patch 1174 (best shown in Fig. 11B) embedded within the optical disk 1170, and (b) a pull tab 1178 that is firmly attached to the patch 1174. Note that in the present figure there is a bonding layer 1182 bonding the patch to the reflective layer 1162. However, in general, the patch 1174 is attached or otherwise bonded to at least one of the sides of the metalized layer 1162 and/or lacquer layer 1158 of the optical disk 1150. For instance, the patch 1174 may be screwed, glued, welded, soldered, clipped or laminated onto the optical disk 1150. Moreover, the patch 1174 and/or the pull tab 1178 may be made of metal, plastic, wood or other suitable material that does not tear easily under tension. The patch 1174 may also be manufactured as part of another layer of the optical disk 1150; e.g., the reflective layer 1162.

Note that there can be various embodiments of a ripcord 1170 that can be mechanically manipulated to provide a physical change to an optical disk of the present

15

20

25

invention. For example, such mechanical ripcords can be in the form of:

- laminated layer with a pull a (substantially as shown in Figs. 11A, 11B);
- (1.2) an error generating push or twist button having, for example, a particular (not shown) arrangement of pins or other pointed objects that etch or scratch a surface of the optical disk 1150 when pressure and/or a twisting force is applied;
- (1.3) a sticker, a strip of metal, an adhesive 10 tape, a pin or other similar object that is effective for generating data access errors when detached from the disk.
  - Accordingly, when such a ripcord 1170 is removed (Fig. 12) from the optical disk or in some way moved or disturbed, the ripcord 1170 also removes, moves, damages and/or carries away with it and/or otherwise modifies the reflective characteristics of the optical disk 1150 so that the data structures thereon generate an increased number of read errors when a read access is attempted. That is, an optical reader (such as an optical readout system 10) is then unable to detect and/or access the information which is present at or near where the ripcord 1170 was located on the optical disk 1150.

In Figs. 13A - 14B, another embodiment of a ripcord is shown, this being a "chemical ripcord" 1370 provided on wherein this disk has disk 1350, corresponding to those of optical disk 1150; i.e., painted surface 1154, lacquer layer 1158, reflective layer 1162 and polycarbonate layer 1166. The chemical ripcord 1370 is 30 incorporated into the optical disk 1350 as an ampule, globule, sac, macroscopic or microscopic chemical carrying liposome made of plastic, wood, metal or other suitable material that can be attached, bonded, glued or laid upon the optical disk as part of the manufacturing process. For 35

10

15

20

25

30

35

example, referring to Figs. 14A and 14B, when pressure is applied (e.g., as represented by force vector 1404), this chemical ripcord is ruptured (or moved, touched, rubbed, or otherwise disturbed) as shown in Fig. 14B. Subsequently, the chemical(s) within is released and/or activated for purposefully damaging the optical disk 1370, and in particular the reflective layer 1162, so that, for example, a greater number (or density or pattern) of optical disk read errors are generated in the area or location adjacent to the now disturbed chemical ripcord 1370. Thus, assuming an optical reader is enabled to detect and/or access the information corresponding to the data structures which are present at or near the location of the chemical ripcord 1370, the optical reader and/or application software associated with the present invention (e.g., as described in Fig. 10) can detect that the information near or adjacent to this location has changed state (e.g., from readable to unreadable) and accordingly, use this state change information for determining subsequent access and/or use of the information residing on the optical disk 1370 as, e.g., is described in Figs 10.

In Figs. 15A - 16B, two additional ripcord techniques for purposefully damaging an optical disk are illustrated, wherein a device external or unattached to the optical disk is used. Accordingly, the optical disk 1550 represented in the presently referenced figures may be a conventional optical disk with the possible exception that the painted surface 1154 may provide an indication as to where the optical disk is to be purposefully damaged. One such disk damaging technique is illustrated that uses an external device 1554 having, for example, a sharp point that can be used for mechanically and purposefully etching, scratching or otherwise damaging the optical disk 1550 as illustrated in Fig. 15B. Referring now to Figs. 16A and 16B, an alternative disk damaging technique is illustrated for a

10

15

20

25

30

35

disk such as 1550. That is, in this technique, a device 1654 that is external or separate from the optical disk 1550 is used for applying a particular chemical(s) 1658 that can purposefully damage at least a portion of the optical disk 1550 so that changes to its reflective characteristics are detected by an optical disk reader. particular, the external device 1654 disclosed has an enclosed chemical compartment 1662 from chemical(s) 1658 are applied to the optical disk 1550, wherein the chemical(s) reacts with the optical disk 1550 for removing or damaging the reflective characteristics of the optical disk so that a greater number of read errors are generated in a predetermined area where the chemical(s) is applied.

Accordingly, in the embodiments of Figs. 15 and 16, an optical reader may be unable to detect or access a substantial amount of the information corresponding to the data structures at or near the use of the external device. Also, the optical reader (and/or other components or modules used in the accessing or processing of information from the optical disk 1550) may determine that the information on the optical disk has changed states (e.g. an indication of a prior use) according to the access errors detected in the predetermined area where the external device was applied (as in step 1052, Fig. 10B).

Additionally, note that an external device as 1554 or 1654 may also include a pin (or other sharp instrument) for both physically and chemically damaging the disk. Moreover, other embodiments for purposefully damaging an optical disk are also within the scope of the present invention. example, the following may be used: a pad, a scratch inducing swatch, or, in a chemical application embodiment, a liposome carrying paste, a receptacle for holding two or chambers separate chemical compounds in more purposefully damaging (more generally, changing) optical

10

15

20

25

30

35

characteristics of the disk when the two or more compounds are combined.

Thus, as described in Figs. 10, once the optical disk is physically changed, altered or otherwise damaged (e.g., step 1044, Fig. 10B) by any of the above techniques, separately or in combination, the user's computer system may then determine the extent to which the information on the optical disk can be accessed or used in a user desired That is, the change and/or damage to the optical disk provides a recognizable state change to, for example, installation routines (e.g., access associated with the optical disk and/or any software application thereon so that a determination can be made as to whether the information on the optical disk has been previously accessed. In addition, such a change and/or damage to the optical disk also provides a user with a visible indication that the data on the optical disk has been accessed. More generally, the purposefully altering or changing of the optical disk provides a mechanism for determining a history of the use of the optical disk, both computationally and by visual inspection of the optical disk.

In Figs. 17A - 21B, converse embodiments to the purposefully damaging embodiments above are illustrated. That is, instead of the ripcord removing information from the optical disk (when the ripcord is manipulated and/or activated), the ripcord in the present embodiments allows additional or different optical disk information to become available (i.e., readable) when the ripcord is manipulated or activated. Thus, in these converse embodiments, instead of the read errors increasing according to an expected profile in a predetermined area of the optical disk, the read errors may decrease according to an expected profile. That is, the ripcord may initially hide or mask the information on the optical disk with a substantially

10

15

20

25

30

35

unreadable covering. However, it is also within the scope of the present invention that such a ripcord covering may be readable and provide different information than that on the optical disk. For example, an optical disk may contain one or more movies for viewing and the ripcord itself may provide information necessary for allowing the movies to be Thus, once the ripcord is removed, thereby viewed. providing access to alternative information, the movie(s) Thus, in this embodiment, a may be viewed only once. detection of a state change is performed without necessarily detecting an expected profile related to generated access errors. It is also worth mentioning here that, as one skilled in the art will understand, similar capabilities may be provided with other duplication protection embodiments of the present invention. example, by using an optical disk coating that changes from opaque to transparent due to, e.g., laser light from an optical disk reader, purposefully masked information on the optical disk can become readable and concomitantly causing a reduction in the number of errors detected and therefore providing a detectable state change in the optical disk.

Referring now specifically to Figs. 17A and 17B (where an optical disk 1750 is shown having similar layers labeled similarly to previous figures), a ripcord is attached or bonded to the exterior surface of the polycarbonate 1166 of an optical disk 1750; e.g., the ripcord 1770 may be laminated, screwed, glued, welded, soldered or clipped to the optical disk 1750. Moreover, the ripcord 1770 may include metal, plastic, wood, paper or other suitable material for hiding information encoded on the reflective layer 1182 of the optical disk 1750. Additionally, note that the ripcord 1770 may be manufactured as part of the optical disk, and can be in the form of a button, sticker, metal strip, adhesive tape, paper patch or other optical disk information mask (or optical distorter) capable of

10

15

20

25

30

35

being removed or rendered transparent to the laser light of the optical reader. Accordingly, when the ripcord 1770 of the present embodiment is removed (Fig. 18) from the optical disk 1750 or in some way moved or disturbed, additional (or alternative) information on the optical disk 1750 becomes readable. Thus, an optical disk reader is then able to detect and/or access this information at or near the previous ripcord location on the optical disk.

Note that additional converse embodiments may also be provided using a chemical approach. Referring to Figs. 19A and 19B (where an optical disk 1950 is shown having similar layers labelled similarly to previous figures), a ripcord 1950 herein includes a chemical carrying container (e.g., an ampule, globule, sac or liposome) attached, bonded, glued or combined with the optical disk 1950 during manufacture. Accordingly, as illustrated in Fig. 20, when this chemical container is removed, disturbed or ruptured, the enclosed chemical(s) is released and/or activated for modifying the reflective characteristics of the optical disk 1950 so that this information becomes readable. example, the chemical sac of the ripcord 1970 may be glued to the exterior surface of the polycarbonate layer with an opaque or colored glue, wherein the chemical(s) within the chemical sac is a solvent for the glue thereby allowing the chemical sac and the glue to be removed when the sac is ruptured and the solvent released. Thus, an optical reader subsequently able to detect and/or access information corresponding to the data structures on the optical disk 1450 which are present at or near the previous location of the ripcord 1970 on the optical disk. Moreover, such a change to an optical disk allows the optical reader (and/or other optical disk accessing components or modules) as well as a person, via visual inspection, to determine that a state change has occurred to the optical disk 1950.

10

15

20

25

30

35

In Figs. 21A and 21B, an embodiment of the optical disk 1750 (Figs. 17) of the present invention is illustrated wherein an external device 2104 is used for applying a chemical(s) to the optical disk, thereby removing the mask or ripcord 1770 attached to the surface of the optical disk 1750 so that optical disk information hidden by the ripcord 1770 is able to be read. Note that the external device 2104 here can be in the form of, for example, a pin, pad, swatch or liposome carrying paste or liquid, wherein the ripcord is either rendered transparent or removed.

In a third collection of embodiments of the present invention, an authentication method and apparatus are provided for authenticating an optical disk. Embodiments of this third collection provide optical disks with purposefully-induced data access errors incorporated therein during manufacturing or at least prior to mass distribution. Moreover, also included in each individual optical disk is authentication information indicating the location of these purposefully induced errors. Thus, when the authentication information accurately identifies the locations of the purposefully induced errors, then the optical disk is assumed to be authentic rather than an illegitimate copy. Note that one particularly noteworthy embodiment in this third collection is provided by attaching "microdots", i.e., microscopic unreadable dots or patches, at various locations throughout the information encoded on an optical disk. Accordingly, if the microdots are sufficiently small so that they obscure or distort only a small area of the optical disk (e.g., approximately 300 microns) then error correction circuitry included within an optical disk access device may be able to correct such errors transparently to a user of the optical disk. Alternatively, for many applications, such as audio (e.g., musical) presentations, the optical disk

10

15

20

25

30

35

information is encoded on the disk redundantly. Thus, even larger microdots may be incorporated without affecting the quality of a presentation of the information accessed from the optical disk.

In a fourth collection of embodiments of the present invention, effectively non-reproducible transaction cards for financial transactions can be provided by the present invention. That is, an optical medium (such as a portion of an optical disk material) is provided on a transaction card along with a mechanism, such as a ripcord, for purposefully damaging the optical medium. Thus, prior to issuing such a transaction card to a user, the optical is purposefully damaged, and the financial medium institution stores an encoding of a mapping of the damaged of the optical medium. and/or undamaged areas Subsequently, the user is provided with the damaged transaction card. Thus, whenever a transaction performed with the transaction card, the damaged optical medium thereon is optically sampled for determining if the samples are consistent with the encoded mapping stored by the financial institution. If so, then the transaction may be allowed. If not, then the transaction is canceled.

In a fifth collection of embodiments of the present invention, authentication of a user requesting a financial transaction is provided. In one such embodiment, a compound that is, for instance, sensitive to touch (e.g., oil reactive, heat sensitive and/or amino acid sensitive) may be layered or coated on an optical medium included on a transaction card (e.g., credit card). Thus, assuming the touch sensitive compound (e.g., a polymer) is sufficiently sensitive so that a user's fingerprint is reliably and accurately duplicated on the compound thereby causing a change in the optical characteristics of the optical medium, then once a fingerprint is provided on the touch sensitive compound, it can be optically sampled for sensing

10

15

20

25

30

35

Next, in step 2216, a process is Internet computer). activated on the user's Internet access device for optically sampling the predetermined touch sensitive area of the optical disk. Then, in step 2220, an encoding of the samples is transmitted to the particular Internet node responsible for determining the authenticity of the transaction. Thus, in step 2224, this particular Internet node compares the samples with a previously stored representation of the user's fingerprint for determining whether the samples are consistent with the fingerprint Accordingly, if the samples representation. sufficiently consistent, then the transaction is completed as in step 2228. Alternatively, if this is not the case, then the transaction is voided as in step 2232.

In the sixth collection of embodiments of the present invention, information related to an item can be encoded on a time sensitive optical medium that changes optical that the information characteristics over time so transforms from readable to unreadable, or from unreadable In particular, certain compounds such as are to readable. disclosed above relating to the first collection of embodiments of the present invention may be utilized in the present collection of embodiments. For example, certain time sensitive items may require corresponding data for labeling, identifying and/or documenting of the items. instance, such items may be cashier's checks or money orders that must be used in a financial transaction in a predetermined time period. That is, by using the present invention, bank routing numbers or other fields may be provided on a time sensitive polymer that becomes unreadable after a predetermined time has expired. prior to becoming unreadable, such identification data may be read by an automatic or computerized check clearing system, whereas after a predetermined time of, e.g., light exposure and/or oxygen exposure, the data becomes

10

unreadable. Additionally, event tickets and/or time sensitive medical supplies may also be similarly labeled with polymers of the present invention.

Accordingly, the present invention has been described at some degree of particularity directed to the exemplary embodiments of the present invention. It should be appreciated, though, that the present invention is defined by the following claims construed in light of the prior art so that modifications or changes may be made to the exemplary embodiments of the present invention without departing from the inventive concepts contained herein.

10

15

20

25

35

## What is claimed is:

- 1. A method of limiting access to data stored on an optical medium, comprising the steps of:
- (a) rotating an optical disk in a disk drive at a selected rotational speed, said optical disk including a substrate encoded with information stored thereon as a plurality of readable data structures and including a reactive compound contacted by a light for reading the data structures, said reactive compound operative in an ambient environment containing oxygen to change optical transmission in response to irradiation by said light for an accumulated duration of time, wherein said light has a beam wavelength within a selected range; and
- (b) directing an interrogating beam of the light having a beam wavelength that is within said selected range toward said substrate layer and through said reactive compound for the accumulated duration of time.
- 2. The method of limiting access to data according to Claim 1 wherein said interrogating beam is directed at said substrate for a continuous interval of time that is sufficient to cause said change in optical transmission.
- 3. The method of limiting access to data according to Claim 1 wherein said interrogating beam is directed at said substrate for a plurality of discrete intervals of time sufficient to cause said change in optical transmission.
- 4. The method of limiting access to data according to Claim 1 wherein said beam wavelength is in a range of 780 to 820 nanometers (nm).
- 5. The method limiting access to data according to Claim 1 wherein said beam wavelength is approximately 650 nanometers (nm).
  - 6. The method of limiting access to data according to Claim 1 wherein said step of directing said interrogating beam at said substrate layer is accomplished

15

20

25

by selectively advancing said interrogating beam radially across an outermost surface of said optical disk until said interrogating beam interacts with said reactive compound for a plurality of discrete intervals of time sufficient to cause said change optical transmission.

- 7. A method of limiting access to data according to Claim 1 wherein said beam intensity is approximately .5 to 1.0 milliwatts (mW) of power.
- 8. A method of limiting access to data according to
  10 Claim 1 wherein said beam wavelength is approximately 780
  nanometers (nm).
  - 9. An optical disk adapted for use in an optical readout system of a computer that includes a light source operative to produce an interrogating beam of light for reading data structures, comprising: (a) reflective layer encoded with information stored thereon as a plurality of data structures that are readable by an interrogating beam of light;
  - (b) a substrate disposed in a confronting relationship with said reflective layer;
    - (c) a film of a reactive compound superimposed over at least some of said data structures, said reactive compound selected to be of a type which is operative to change physical characteristics in response to a selected stimulus, thereby to affect readability of the data by said interrogating beam of light.
    - 10. An optical disk according to Claim 9 wherein said reactive compound is interposed between said reflective layer and said substrate.
- 11. An optical disk according to Claim 9 wherein said reflective layer is contoured to include a sequence of pits and lands which define said plurality of data structures, said reactive compound superimposed over at least some of said pits and lands.

20

25

- 12. An optical disk according to Claim 9 wherein said reactive compound is supported on an outer surface of said substrate and has a thickness in a range of approximately 0.14 to 0.6 microns.
- 13. An optical disk according to Claim 9 wherein said stimulus is selected from a group consisting of visible light, infrared light, an ambient environment containing light and air.
- 14. An optical disk according to Claim 9 wherein said stimulus is light and wherein said reactive compound is a photoreactive material.
  - 15. An optical disk according to Claim 9 wherein said reactive compound comprises selected from a spiropyran class of photochromic compounds.
  - 16. An optical disk according to Claim 15 wherein said reactive compound comprises 6-nitro-1'3'3'-trimethylspiro[2H-1-benzothiopyran-2,2'-indoline].
  - 17. An optical disk according to Claim 9 wherein said reactive compound is operative to change to an optically darkened state in response to an interrogating beam wavelength of approximately 780 nanometers (nm) and thereafter return to an optically clear state in response to irradiation by a beam of light having a wavelength of approximately 337 nanometers (nm).
  - 18. An optical disk according to Claim 9 wherein said stimulus is an ambient environment containing light and oxygen and wherein said reactive compound has the chemical formula:

25

5 H C C CH3
H C C CH3
H C C C CH3

## COMPOUND 1

19. An optical disk according to Claim 9 wherein said stimulus is an ambient environment containing light and air and wherein said reactive compound has the chemical formula:

- 20. An optical disk according to Claim 9 wherein said stimulus is air and wherein said reactive compound is operative for an accumulated duration of time to oxidize and alter an optical characteristic of the compound.
  - 21. An optical disk according to Claim 9 wherein said reactive compound is operative to change from an optically transparent to an optically opaque condition wherein said reactive compounds absorbs light having a wavelength within a selected range.
  - 22. An optical disk according to Claim 21 wherein said wavelength is approximately 780 nanometers (nm).
- 30 23. An optical disk according to Claim 21 wherein said wavelength is approximately 650 nanometers (nm).

## SUBSTITUTE SHEET (RULE 20)

10

15

20

25

30

35

- 24. An optical disk according to Claim 9 wherein said reactive compound is a chemically reduced form of a dye.
- 25. An optical disk according to Claim 9 wherein said reactive compound is selected from a group of dyes consisting of methylene blue, brilliant cresyl blue, basic blue 3 and toluidine blue 0.
- 26. In an optical disk for use in an optical readout system of a computer wherein said optical disk includes an inner substrate layer having a substrate surface encoded with information stored thereon as a plurality of data structures and an outer layer and wherein said optical readout system includes a disk drive operative to rotate the optical disk at a selected rotational speed, a light source operative to produce an interrogating beam of light at a selected beam wavelength and at a selected beam intensity and to direct said interrogating beam of light at the data structures, and a detector operative to collect a returned component of said interrogating beam and to output signal in response thereto, an produce comprising a film of reactive compound improvement superimposed over at least some of said data structures, said reactive compound operative to change its physical characteristics in response to a selected environmental stimulus thereby to affect readability of the data by the interrogating beam of light.
- 27. The improvement of Claim 26 wherein said reactive compound is responsive to irradiation by the interrogating beam for an accumulated duration of time to change physical characteristics thereby to mask said data structures and to render said data structures undetectable by the optical readout system.
- 28. An article of manufacture adapted to be encoded with data and further adapted so that duplication of the data by an optical scanning machine may be inhibited, comprising:

## SUBSTITUTE SHEET (RULE 28)

10

15

20

25

- (a) a substrate fabricated from a selected material and having a substrate surface which contains the data; and
- (b) a reactive compound coating at least a portion of said substrate surface, said reactive compound operative to change from an optically transparent state to an optically opaque state in response to irradiation for an accumulated duration of time by infrared light having desired characteristics thereby to prevent light from the optical scanning machine from penetrating said reactive compound and to render the data undetectable by the optical scanning machine.
- 29. A method of limiting the use of information stored with an optical medium, comprising:

providing, to an optical reader, the optical medium having information for performing a desired action;

determining whether an expected profile of a purposefully induced change in the access of the information is detected;

performing the desired action using the information when said expected profile is detected; and

prohibiting said step of performing when said expected profile is not detected.

- 30. A method as claimed in Claim 29, wherein said optical medium is one of a compact disk and a digital versatile disk.
- 31. A method as claimed in Claim 29, wherein said step of determining includes detecting said purposefully induced change as one of: a distinctive pattern of errors, and a distinctive pattern of an absence of errors.
- 32. A method as claimed in Claim 31, wherein said step of detecting includes detecting one of the distinctive patterns by determining a related to one of the errors and the absence of errors.
- 33. A method as claimed in Claim 29, wherein said 35 step of determining includes:

10

15

20

25

sampling locations on the optical medium for detecting data access errors, wherein location data related to the detection of the data access errors is obtained;

comparing the expected profile with the location data for detecting said change in the access of the information.

- 34. A method as claimed in Claim 33, wherein said step of comparing includes evaluating a function dependent on one of: a number of errors detected, a relative number of errors detected, a pattern of errors, a density of errors detected and a location of errors detected.
- 35. A method as claimed in Claim 34, wherein a result of said function indicates that said expected profile is detected when there is at least one of: a minimum threshold number of errors detected, and a minimum threshold density in the number of errors detected.
- 36. A method as claimed in Claim 34, wherein a result of said function indicates that said expected profile is detected when there is at least one of: a maximum threshold number of errors detected, and a maximum threshold density in the number of errors is detected.
- 37. A method as claimed in Claim 33, wherein said step of sampling includes detecting data access errors not capable of being corrected by error correction modules receiving data via the optical reader.
- 38. A method as claimed in Claim 29, further including a step of damaging the optical medium by one of: a chemical reaction and a mechanical activity;

wherein said step of damaging is for obtaining said expected profile.

- 39. A method as claimed in Claim 38, wherein said step of damaging by a mechanical activity includes changing a reflective characteristic of the optical medium by one of: tearing and etching a layer of the optical medium.
- 40. A method as claimed in Claim 39, further including a step of encoding one of a damaged and undamaged

10

15

20

25

30

portion of the optical medium for identifying a financial transaction card having said optical medium, after said step of damaging is performed.

41. A method as claimed in Claim 29, wherein said step of performing includes correcting data access errors detected as part of said expected profile;

wherein said step of correcting is performed during said performing of the desired action.

- 42. A method as claimed in Claim 41, wherein at least some of said access errors are induced by microdots.
  - 43. A method as claimed in Claim 42, wherein said microdots each have a size of approximately less than 1000 microns.
- 44. A method as claimed in Claim 29, further including a step of creating access errors as an instance of said expected profile prior to performing said step of providing.
- 45. A method as claimed in Claim 44, wherein said step of creating includes incorporating into the optical medium, a means for authenticating the optical medium, wherein the information on said optical medium includes one of an audio presentation and a multimedia presentation.
- 46. A method as claimed in Claim 38, wherein said step of damaging the optical medium includes changing a reflective characteristic of the optical medium by one of: exposing the optical medium to a reactive chemical, rupturing a chemical container attached to the optical medium, and exposing a predetermined part of the optical medium having a light sensitivity to an effective amount of light for changing the reflective characteristics of the optical medium.
- 47. A method as claimed in Claim 38, wherein said step of damaging includes removing an item attached to the optical medium.

10

15

20

25

- 48. A method as claimed in Claim 29, further including a step of reducing access errors for obtaining said expected profile.
- 49. A method as claimed in Claim 48, wherein said step of reducing includes performing one of: a chemical reaction and a mechanical activity for changing a reflective characteristic of the optical medium.
- 50. A method as claimed in Claim 49, wherein said step of performing includes removing an attached layer from the optical medium.
- 51. A method as claimed in Claim 49, wherein said step of performing includes changing a reflective characteristic of the optical medium by one of: purposefully exposing the optical medium to a chemical rupturing a chemical container of the optical medium, and exposing a predetermined part of the optical medium having a light sensitivity to an effective amount of light for reducing the access errors.
- 52. A method as claimed in Claim 29, wherein said step of performing includes conducting a financial transaction, wherein said optical medium is included on a card for conducting the financial transaction.
- 53. A method as claimed in Claim 52, wherein said step of determining includes reading identifying data on said card for identifying a previously stored representation of said expected profile.
- 54. A method as claimed in Claim 29, wherein the information includes one of: graphical data, video data, audio data, text data and a software program.
- step of determining includes attempting to access a portion of the information residing within a predetermined part of the optical medium where the expected profile resides, wherein the predetermined part includes a minority of a total storage capacity of the optical medium.

20

25

30

- 56. A method as claimed in Claim 29, further including a step of deactivating an error correction module.
- 57. A method as claimed in Claim 56, wherein said step of deactivating is performed prior to each performance of said step of determining.
  - 58. A method as claimed in Claim 57, further including a step of reactivating the error correction module after said step of determining.
- 59. A method as claimed in Claim 29 further including steps of:

encoding said purposefully induced change; and outputting said encoded change to a user of the optical medium waiting to perform the desired action.

- 60. A method as claimed in Claim 59, wherein said step of encoding includes encrypting said purposefully induced change together with identification data related to at least one of: an identity of the user, and an identity of at least one component of a device used for processing the information on the optical medium.
  - 61. A method as claimed in Claim 60, wherein said step of encrypting includes determining an identifying code for one of a central processing unit and a peripheral processing unit as said at least one component.
  - 62. A method as claimed in Claim 29, wherein said step of providing includes purposefully inducing a change in access errors at each of one or more locations of the optical medium for instantiating said expected profile.
- 63. A method as claimed in Claim 62, wherein said step of purposefully inducing includes:

removing the optical medium from the optical reader; altering an optical characteristic of the optical medium; and

providing, again, said optical medium to the optical reader.

15

20

25

35

64

- 64. A method as claimed in Claim 62, wherein said step of purposefully inducing includes changing one of an optical reflectance and an optical transmittance.
- 65. A method as claimed in Claim 62, wherein said step of purposefully inducing includes one of rendering unreadable an initially readable portion of the optical medium and rendering readable an initially unreadable portion of said optical medium.
- 66. A method as claimed in Claim 62, wherein said step of purposefully inducing includes providing an image of a body part on a touch sensitive portion of said optical medium.
  - 67. A method as claimed in Claim 66, further including a step of comparing a representation of said provided image with a previously stored representation of a body part image for determining a consistency between said provided image representation and said previously stored image representation.
  - 68. A method as claimed in Claim 67, wherein said step of comparing includes a step of transmitting said representation of the provided image on a communications network for performing electronic commerce.
  - 69. A method as claimed in Claim 66, wherein said touch sensitive portion includes a compound reactive to one of heat, pressure, and a bodily produced substance.
  - 70. A method as claimed in Claim 29, wherein said step of determining includes identifying said optical medium using an inputted code describing the expected profile.
- 30 71. A method as claimed in Claim 70, wherein said inputted code was previously provided to a user desiring to perform the desired action.
  - 72. A method as claimed in Claim 70, wherein said inputted code was output during a previous performance of said step of determining.

10

20

25

30

73. A method of limiting the use of information stored on an optical medium, comprising:

providing, to an optical reader, an optical medium having information for performing a desired action;

detecting an expected profile of a change in access errors for the information on the optical medium;

comparing an encoding of the change with a user input; performing the desired action using the information when said encoding provides a favorable comparison with the user input; and

prohibiting a performing of the desired action when said encoding provides an unfavorable comparison with the user input.

74. A method as claimed in Claim 73, further including a step of encrypting together a representation of said change and identification data related to at least one of: an identity of the user, and an identity of a device for accessing the information on the optical medium;

wherein a result of said step of encrypting yields said encoding.

- 75. A method as claimed in Claim 74, wherein said step of detecting includes determining said change in the access errors by mapping locations of the access errors in at least one predetermined portion of the optical medium.
- 76. A method as claimed in Claim 75, wherein said predetermined portion extends to only a minority of the total data storage capacity of the optical medium.
- 77. A method as claimed in Claim 73, wherein said step of determining includes using a representation of locations of the access errors in an encryption process for obtaining said encoding.
  - 78. A method as claimed in Claim 73, wherein data of said user input was obtained by the user from a previous attempt to access the information on the optical medium.

15

20

25

30

79. An apparatus for limiting the use of information stored with an optical medium, comprising:

an optical medium having stored information, wherein said information is used in performing a desired action;

means for producing a change in the access errors encountered when accessing data locations for information on the optical medium, wherein the change corresponds with an expected profile;

means for detecting whether an instance of the 10 expected profile has occurred;

means for determining when to perform the desired action using an output from said means for determining whether said instance has occurred.

- 80. An apparatus as claimed in Claim 79, further including means for performing the desired action when the instance of the expected profile is detected.
- 81. An apparatus as claimed in Claim 79, wherein said means for performing includes one of: means for loading software onto a computer, means for presenting a presentation, and means for conducting a financial transaction.
- 82. An apparatus as claimed in Claim 79, further including:

means for prohibiting an activation of the desired action when an instance of the expected profile is not detected.

83. An apparatus as claimed in Claim 79, further including:

means for performing the desired action until an instance of the expected profile is detected.

84. An apparatus as claimed in Claim 83, wherein said means for performing the desired action includes means for reading identification data from said optical medium, wherein said optical medium is provided on a financial

10

15

20

25

transaction medium, and said optical medium is one of: light sensitive and oxygen sensitive.

67

- 85. An apparatus as claimed in Claim 84, wherein identification data includes bank routing data.
- 86. An apparatus as claimed in Claim 79, wherein said optical medium includes a digitally encoded optically reflective material.
- 87. An apparatus as claimed in Claim 86, wherein said optically reflective material is included in one of a compact disk, digital versatile disk, and a financial transaction card.
  - 88. An apparatus as claimed in Claim 79, wherein said desired action includes one of: loading information into a computer memory, performing an audio presentation, performing a multimedia presentation, and performing a financial transaction.
  - 89. An apparatus as claimed in Claim 79, wherein said means for detecting includes means for sampling data in one or more locations of the optical medium.
- 90. An apparatus as claimed in Claim 79, wherein said means for producing is attached to said optical medium.
- An apparatus as claimed in Claim 79, wherein said means for producing includes one of: a means for increasing access errors, and a means for decreasing access errors.
- 92. An apparatus as claimed in Claim 91, wherein said means for increasing access errors includes one of: a chemical sac, a ripcord, an etching means for etching a surface of the optical medium, and an embedded light reactive chemical in the optical medium.
- 93. An apparatus as claimed in Claim 91, wherein said 30 means for decreasing data access errors includes one of: a data mask attached to the optical medium, and a chemical sac attached to the optical medium.
- 94. An apparatus as claimed in Claim 79, wherein said means for producing includes an instrument detached from 35

10

15

20

25

35

said optical medium, wherein said instrument changes an external surface of said optical medium when applied to the optical medium.

- 95. An apparatus as claimed in Claim 94, wherein said instrument includes one of: means for scoring, and means for removing a layer of said optical medium.
- 96. An apparatus as claimed in Claim 79, further including an encoding means for encoding a representation of the change in the access errors, wherein said means for encoding includes means for outputting to a user encrypted data including an encryption of a combination of: (a) the change in the access errors, and (b) at least one of: an identification of the user and an identification a device for accessing the information on the optical medium.
- 97. An apparatus as claimed in Claim 96, wherein said means for outputting instructs a user to copy said encrypted data.
- 98. An apparatus as claimed in Claim 79, wherein a user desiring access to the information activates said means for producing prior to gaining access to the information.
- 99. An apparatus as claimed in Claim 79, further including storage for storing a representation of the change in the access errors, wherein said representation is referenced in said storage using an identification of a user having the optical medium.
- 100. An apparatus as claimed in Claim 99, wherein said representation is used in a verification process of a financial transaction.
- 30 101. A method of limiting access to stored data on an optical medium, comprising:

inserting the optical medium into an optical medium access device for accessing information in at least one of a predetermined first storage portion and a predetermined second storage portion of the optical medium;

10

15

25

35

activating a desired computer application, wherein to perform said application, information in said predetermined second storage portion must be used;

purposefully inducing a change in the first storage portion, wherein said change is irreversible;

obtaining a response indicative of whether the purposefully induced change exists; and

determining whether to use the information in said predetermined second storage by accessing said response indicating the existence of said change.

- 102. A method as claimed in Claim 101, wherein said step of purposefully inducing includes damaging an optical characteristic of the first storage portion.
- 103. A method as claimed in Claim 101, wherein said step of purposefully inducing includes one of: removing a layer from the first portion, causing a layer of the first portion to become opaque, marring a layer of the first portion, and chemically distorting an optical characteristic of the first portion.
- 20 104. A storage medium having limited access, comprising:
  - a first storage portion of the storage medium, wherein said first storage portion includes one or more data storage locations, wherein the locations are related to a data accessibility profile;
  - a means for changing the accessibility of data at the locations, where the change is purposeful and substantially irreversible;

wherein when said means for changing is applied to the locations, said profile is obtained.

- 105. A storage medium as claimed in Claim 104, wherein said storage medium is an optical disk.
- 106. A storage medium as claimed in Claim 104, wherein said means for changing includes a detachable portion of the storage medium, wherein the data accessibility profile

10

15

20

25

30

is detected during an access of the locations when said detachable portion is detached from the storage medium.

- 107. A storage medium as claimed in Claim 104, wherein said means for changing generates one of a decrease and an increase in the number of errors during access to the data at the locations.
- 108. A storage medium as claimed in Claim 104, wherein data in a second storage portion of the storage medium is accessible in response to an indication that said data accessibility profile exists.
- 109. A method of limiting access to stored data on a storage medium, comprising:

inserting the storage medium into a storage access device for accessing information in at least one of a predetermined first storage portion and a predetermined second storage portion of the storage medium;

activating a desired computer application, wherein to perform said application, information in said predetermined second storage portion must be used;


purposefully inducing a change in the first storage portion;


selecting a sampling of a plurality of the storage medium locations, wherein the locations of the sampling are selected so that there is a predetermined density of samples within the first storage portion;

detecting said change by accessing the locations of the sampling;


obtaining a response indicative of whether the purposefully induced change exists; and

determining whether to use the information in said predetermined second storage by accessing said response indicating the existence of said change.






SUBSTITUTE SHEET (RULE 26)





SUBSTITUTE SHEET (RULE 20)




SUBSTITUTE SHEET (RULE 20)

4/19







**SUBSTITUTE SHEET (RULE 28)** 



09/646/4/





8/19




Fig. 11A






Fig. 11B

**SUBSTITUTE SHEET (RULE 26)** 










FIG. 12





SUBSTITUTE SHEET (RULE 26)

PCT/US97/08842






Fig. 14A




Fig. 14B

## SUBSTITUTE SHEET (RULE 26)

12/19




Fig. 15A






Fig. 15B





14/19





Fig. 17A



SUBSTITUTE SHEET (RULE 26)

09/646/4

15/19





Fig. 18








Fig. 19B

## 17/19






Fig. 20


Fig. 21A





SUBSTITUTE SHEET (RULE 28)

## 19/19



- FROM

(TUE) 08. 01'00 12:02/ST. 12.00/NO. 3561892125 P 7

PTG/SB/01 (8-95)
Approved for use through 10/31/98 CMB 3651-0032

Patent and Trademark Office: U.S. DEPARTMENT OF COMMERCE Type a plus sign (+) Inside that box -Attorney Dooket Number 3899-2-PUS 00/PTO Rev. 6/95 U.S. Department of Commerce Patent and Trademark Office MCLAUGHLIM, MOIK Fort Named Invantor **DECLARATION FOR** COMPLETE IF KNOWN **UTILITY OR DESIGN** Application Number PATENT APPLICATION Filing Date Declaration Submitted with Initial Filing OR 🗖 Group Art Link Examener Name As below named inventor, I hereby declare that:: My maldence, post office address, and citizenship are as stated below next to my na t believe i am the original, first and sole inventor (if only one name is listed below) or an onginal, first and joint inventor (if pluret ne Itsaed below) of the subject matter which is claimed for which a patent is sought an the invention entitled: "COPY PROTECTABLE OPTICAL MEDIA DEVICE AND METHODOLOGY THEREFOR" (Title of the Invention) is attached hereto OR as Unligd States Application Number of PCT International 05 June 1997 窗 WEST RIGHT OF (MINEROLOTYYY) PCT/US97/08842 and was emerical (MAKODAYYYY) Application Number I have by state that I have reviewed and understand the contents of the above identified specification including the claims, as amended by any amendment specifically referred above. eledge the dusy to disclose information which is material to patentability as defined in Tide 37 Code of Federal Regulations, § 1.56. I hereby claim foreign pilotify benefits under Title 35, United States Code § 119 (a)-(d) or § 365(b) of any tonign explication(c) for patent or inventor's certificate, or \$305(a) of any PCT international application which designated at least one country other than the United States of Appoints, State below and figure also liketified below, by checking the box, any foreign application for patent or inventor's certificate, or of any Pct International application through a filling date before that of the application on which priority a claimed. Certified Copy Attached? Foreign Filing Date Yes Additional foreign application numbers are listed on a supplemental priority sheet planted freeto. I hereby claim the benefit endor Trite 35, United States Code § \$19(e) of any United States provisional application(e) lasted below Filing Date (MM/DID/YYYY) Application Number(s) Additional provisions application numbers are listed on 8 Merch 14, 1997 30/340,724 Borden Hour Statisment: This form is exhaused to take 4-hours to complete. Time will very depending upon the regard account of loos you are required to complete this form should be earn to the Chell Information officer, Patich and Track account of Issue you are required to complete this form should be earn to the Chell Information officer, Patich and Track DO NOT SENS FEES OR COMPLETED FORMS TO THIS ADDRESS. SENSO TO. Auditoric Commissions for Patic

Type a plus sign (+) inside this box	· 🗆 🔝											
DECLA	RATIO	N					P	age 2				
I hereby claim the benefit under TB application designating the United Stands designating the United Stands designating the United Stands designation of Code § 112.1 acknowledge the day § 1.58 which became available but	States of A little of PCT	murico, Estad he I International as	pplicatio	i, incolor a n in lite m	s the su soner pr	ovyden pi placi wai	the first	n or ere o peregrapi Tota 37. C	eathas Cr 1 of Tille Jodes of F	ovs a 35. L eden	ppincero Intend S al Resoul	abena babes
U.S. Parent Application Number		PGT Parent Number			Parent (NAM)	Filing Da DDMYYY	he- )		Pacont P (If a	atent pplice		•
Additional U.S. or PCT Internal As a named Inventor, I hereby app Patent and Trademark Office conn	pint the foll	owing attorney(s								all bu	sineas l	n the
K Firm Name	SH	ERIDAN RO	SS P.	C.			ationer union	_ or label				
OR List attorney(a) and/or agent	(a) name t	nd registration n	umber i	elow:					L			
Name		Registral				Mayn	-			3	giskako Kumber	
ZINGER, DAVID F.		29,12				RIPA CR	OWLEY				33,374 35,536	
GROSETH, CRAIG C.		31,71			en, Len ek, XXS				ł		33.005	
TOMPKINS, MICHAEL L. BLAKELY, TODO P.		31,32				GLAS W					37,739	
CONNELL GARY J		32,02	-	KUGL	R aru	CE A.			1		38,942	
CROOK, WANNELL M.		31,07		BRUN	ELU, RO	BERT R					39,617	
X Additional attornoy(s) and/or a	inute) on:	ned on a supple	mente) :	rice! alta	had her	eto-						
Please direct all correspondence to:	L ;	Customer Number er					OR (		III in con ddess b		edence	
Name JOSEPHE.	COVARIK											
Address 1580 BRO	ADWAY, S	UITE 1200										
Address						7			7	904	02-514	•
City DENVER					State		LORADO	Fex	(393) B	_		
Country UNITED STATES OF a 1 harmby ductave that all statement	RIMERICA		ghane		NS3-9704							
I heraby doctore that all statement believed to be true: and further the punishable by fine or brantscorren ency jeopardize the validity of the a	il litetia sila 2. or both. i	Apments were M under Section 19	oose wat Oo i of T	n sie knor Ne 16 of								
Home of Sole or First Inventor.	T					illion has	been Re	d for this i	ansignod			<b>,</b>
Given Name Merk	_1	Afficial (relia)	T	Fami		ct aughtr					116x g. 4r.	<u> </u>
Inventor's Signature	<del></del>						Dete					
Residence City Batton Rouge		State	Louisi	B718	6	ountry	USA	- 1	Mirensh	ip	USA	
Post Office Address 5514 S	Pointer Co	urt .										
Post Office Address												
City Salor Rouge	State	Louisiana	Zip	70808		Country	USA		Applica Author			

	B SWS DOX										-		
Q	ECLAF	ITAS	ON					AD	Supplement	tel Sh	usqs)		
terne of Additional Join	4 hwarter, i	Sult.						A pelibo	n has been	med for			entor
Given	· · · · · · · · · · · · · · · · · · ·			Modate Initial	δ.	Ferrity Name	Lac	uritz.			:	deffin og dr.	1
proceedings. Signature							<b>.</b>		Date	Les	conship	USA	
	ortino			State	Californ	48	Con	may U	SA	10	OEU340	USK	
Post Office Address	10952 8#	manca 0	live										
Post Office Address	-						Т	Country	USA	<del>- 1</del> .	Applicant	7	
City Cuperano	l l	State	Californi	b	ZP	95019		Commy	Uan		Authority		
Name of Addisonal Jos	ni inventor,	fany:					C	A petite	on has been	filed to	t this unsig	yned m	eracr
Given				Masses	1	Family Name	Sm					Seffitx e.g. Jr	
Name Jerry				initial		I THE STREET	j 3171			_		<u> </u>	
ispendar's Signature				-	-				Date	ļ		-	
September 1									ĺ				
Residence Little				State	Colora	- do	Co	undry I	USA	0	kaenohip	LESA	
City					<u> </u>			L				ــــــــــــــــــــــــــــــــــــــ	
Post Office Address	5690 W.	Ro-dank	Ave.										
Post Office Address	<u> </u>				,				T		Applicant	_	
City Linkston	- 1	State	Celorad	to :	Zip	60120	1	Corniga	USA		Authority	<u> </u>	
Name of Additional Jo	wit Inventor,	if eny.	T				C	] A pelli	ion has bee	n filed fo	y Pak yasi	~~~~	rentar
Glyan	wé Inventor,	if eny.		) Alichida Fratical		Family Name	1	A petiti sidon	ion has bee	n filed fi	y Pak unci	gned im Suffer e.g. in.	rentar
	unt inventior.	if eany.	ا (ا				1		Clate	n filed fo	y Pile uncl	Suffer	rentor
Cheef Name James Inventor's Segurature	cost inventor.	if eany.	_ رو			Name	<b>W</b>				y Me unci	Suffer	restor
Cheef Name James Inventor's Segurature	\Q\ \\	)_(	(J)	Instal	_ ح	Name	<b>W</b>	aksan				Suffer e.g. Jr.	restor
Chest Name James Inventor's Segnature Hoskionee City B	loudities	)_(	(L)	Instal	_ ح	Name	<b>W</b>	aksan	Oate 8/260		itizenskip	Suffer e.g. Jr.	resitor
Olvering James Inventor's Segnature Residence City B Post Office Address	loudities	)_(	Road	Institute   Q	_ ح	Name	<b>W</b>	aksan	Oate 8/260			Suffer e.g. Jr.	resilor
Glven Name James Inventor's Signature Houldonce Cay B Post Office Address Popt Office Address	iousides 5424 S.	Roulder State		Institute   Q	Coder	Name	]a	eldori Surriny Course)	Oate 8/260		Applicants Authority	Suffer e.g. in USA	
Gleen James Immentor's Signature Hacidence City Frost Office Address City Bookles Name of Additional Ju Gleen	Couldes Sept 6.	Roulder State		Institut	Coton	Name  so  so  so  Family	[Ca	Country A post	Date 8/260 USA		Applicants Authority	Suffer e.g. in USA	westor
Gheer Name James meetor's Segrature Haddence City B Post Office Address City Boulder Name of Additional Ju	Couldes Sept 6.	Roulder State		State of the state	Coton	Name do	[Ca	eldori Surriny Course)	Date 8/260 USA	o c	Applicant Authority or this unit	Suffer of the Su	ventor 1
Gleen Name James Inventor's Signature Houldonce City B Prost Office Address Popt Office Address City Boulder Name of Additional Ja Gleen Nome J. Bucklard Inventor's Signature	Couldes Sept 6.	Roulder State		Institut	Coton	Name  80303  Family Name  MARKETTE		Course) A post	Date 8/2000 USA USA	o c	Applicants Authority	Suffer of the Su	ventor 1
Gleen Name James Inventor's Signature Houldonce City B Post Office Address Post Office Address City Boulder Name of Additional J. Gleen Name J. Busiliard Inventor's Signature Residence City J	iculties   Gold E. Gol	State  # store	Cotors	Saate do Middle 1999	Codes	Name  80303  Family Name  MARKETTE		Course) A push	USA USA Date	o c	Applicant Authority or this unit	Suffer of the Su	ventor 1
Gleen Name James Inventor's Signature Houldonce City B Prost Office Address Popt Office Address City Boulder Name of Additional Ja Gleen Nome J. Bucklard Inventor's Signature	iculties   Gala 6.	State  # store	Cotors	Saate do Middle 1999	Codes	Name  80303  Family Name  MARKETTE		Course) A push	USA USA Date	o c	Applicantship Applicantship Of this unit	Suffice of the Suffic	ventor 1
Gleen Name James Inventor's Signature Houldonce Cay B Post Office Address Post Office Address Post Office Address Signature Inventor's Signature Inventor's Signature Inventor's Signature Post Office Address Post Office Address	iculties   Gala 6.	State  # store	Cotors	Institute   Inst	Codes	Name  80303  Family Name  MARKETTE		Course) A push	USA  Date    USA  Date  USA	o c	Applicant Authority or this unit	Suffice C. J. USA  USA  Suffice C. J. USA	ventor 1
Gleen Name James Inventor's Signature Houldonce Cay B Post Office Address Post Office Address City Boulder Name of Additional J. Gleen Name J. Busilisrd Inventor's Signature Post Office Address Post Office Address Post Office Address	Countries   Sales & Sa	State State State State State State	are Manys	Seate	Zip   Zip   Stary   Zip   Zi	Name  Rosos  Roso  Rosos  Roso  Rosos  Roso  Rosos  Rosos		Country A politicary Country Country Country	USA USA USA USA USA USA	o c	Applicantable Applicantable Applicantable Applicantable Applicantable Applicantable	Suffice C. J. USA  USA  Suffice C. J. USA	ventor 1

X

, L.

5157 EPGEUE

TUE: 58. 07 EC 12 C2/ST 12 CD/NC 355/892125 P 7

PTO/SB/01 (8-95) Approved for use through 10/31/96 OMB 0651-0032 Type a plus sign (+) Incide this box --Palent and Trademark Officer U.S. DEPARTMENT OF COMMERCE 3999-2-PUS DOPTO U.S. Department of Commerce Attorney Docket Number Rev 5/95 Patent and Trademark Office MCLAUGHUN, MEZH First Named Inventor DECLARATION FOR COMPLETE IF KNOWN UTILITY OR DESIGN Application Number PATENT APPLICATION Fring Date Group Art Unit Declaration 少訊 Declaration Supmitted with Superisted after Initta Filing Initial Filing Examiner Name As below named inventor, heraby declare that: My residence, gost office address, and oftenship are as stated below next to kny name I believe I am the original, first and sole inventor (If only one name is listed below) of an original. Stat and joint Inventor (If plural trames are itsed below) of the subject matter which is desimed for which a petent is sought on the invention onlined. "COPY PROTECTABLE OFTICAL MEDIA DEVICE AND METHODOLOGY THEREFOR" (Title of the invention) the specification of which is absched hereto 05 June 1997 as United States Application Number of PCT International was fied on (MM/DD/YYYY) (if applicable) Application Number PCT/US97/38842 and was emended on (YYYYIOONMA) I hereby state that I have reviewed and understand the contents of the above identified specification. Including the claims, as amended by any amendment specifically referred above. I acknowledge the duty to disclose information which is material to obtain billing as defined in Title 37 Code of Federal Regulations § 1.56 I hereby cash foreign priority benefits under Title 35, United States Code § 118 (a)-(d) or § 365(b) of any foreign application(s) for patient or inventor's certificate or \$385(a) of any PCT international application which designated at least one country other than the United States of America, listed below and have also identified below, by checking the box, any foreign application for patent or inventor's critificate or of any Pol international application having a filling date before that of the application on which broatly is claimed. Foreign Fliing Oate Cartifled Copy Attached? Prior Foreign Application Country Prionty

Momosifa)		(144-000	Q. 010 11 103	Yes	No
☐ Additional foreign applicate	on numbers are listed on a subj	Slanventaj pravity sheet adached	hereto.		
thereby dam the benefit under	Tide 35 United States Code §	119(a) of any United States prov	isional application	n(8) hated aslow	
Application Mumber	(s) Finn	Date (MM/DD/YYY)			
50/G40,724	March 14, 194	97		Addressen null application null are listed on a supplemental p sheet attached	nonky

Bursen Hour Sustament. This form is estimisted to take 4 hours to complete. Thes will very depending upon the needs of the individual case. Any comments on the smouth of time you are required to complete this form should be sent to the Chief information officer. Patent and Trademant Office. Weshington, OC 20231 DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO Assistant Commissioner for Patents Washington, OC 20231

THE PARTY OF THE P

(TUE) 08 (1'03 12 03/ST 12:00/NO 3561392125 F 9

Type a plus sign (+) inside this box . ADDITIONAL INVENTOR(8) DECLARATION Supplemental Sheet Name of Additional Joint Inventor, if any, A cetition has been filed for this unsigned inventor Miciglia Family Hiery Lackritz. Indias Nourse Nome **e.**g. Jr. Date inventor's Signaturo 8/10/00 California Residence City Cupertino State Country USA Clazenship USA Post Office Address 10952 Barranca Drive Post Office Address Applicant 95019 Cupertino State Callfornia ΖÞ Country USA City Authority Name of Additional Joint Inventor, if any A petition has been filed for this unargred inventor Given Nacidie Family Suffix Name. initial Name Jerry Date Inversion's Sicratore Ciazensino LINA Colorado Country USA Residence Littleton Stale City 5690 W. Rowland Ave Pour Office Address Post Office Address Applicant Littleton Colorado Z)p 80120 Country USA Authority Name of Additional Joint Inventor, if any. A potition has been filed for this unaligned inventor Suffee Giver Middle Parely Weldon Name initial Name 43 11 Deta inventors Signature Colorado Country USA Citizenship USA Residence City Post Office Address 6424 S. Boukser Road Post Office Address Applicant 80303 City State Colorado Zφ COURTRY USA Authority Name of Additional Joint Inventor, if any A peddon has been fled for this unsigned inventor Suffic Given Middle Farryly Name J Brantero indai eg Ji. Date nventor's Elgnature Country Citizenship USA Residence City State Maryland USA Annapolis Post Office Address 53 Genzy Court Post Office Address Apolicant 21403 Country USA City Annaopés Starte Maryland Ζœ Authority [X] Further applicants and/or (further) inventors are indicated on another continuation sneet Form PCT/RO/101 (continuation races)(July 1998)(form duplicated by Sheridan Ross P.C.-jman) See Notes to the request form FROM

(TUE) 98. 01' CO 12:02/ST 12:00/NO. 3561892125 P 7 PTO/58/01 (6-95)
Approved for use through 10/31/96 OMB 0851-0032

				3		Patent and Tradema	R Ginds.			
- 3/P1	plus sign (+) Incid			nent of Comme	rce Atto	arriey Docket Number		3696	2-PUS	
	5/95	Fale	ent sac	Trademark Of	nce i	k Named Inventor		MCL	AUGHUN, Ma	<b>'</b> t
	DECLA	RATI	ON	FOR		COM	PLETEIF	KNOWN		
	UTILITY				Apr	disation Number				
	PATENT	APP	LIC	ATION	Freis	ng Daie				
	Declaration	OR	П	Declaration	, –	ayo Ari Unit				
₫.	Submitted with Initial Filing			Submitted aft Initial Filing		amurer Hame				
1 in	polieve I am the o	office ad riginal, fo subject r	dress. st and nation	and citzenship sole inventor (i which it daims	only one of for which	name is listed below) or an ongit is petent to sought on the Invention DEVICE AND METHER of the Invention)				ni mames are
]	is absched here OR was filed on (MW/DD/YYYY)			05 Juna 1997		as United States Application	Number o	r PCT Inc	lenoitema	
	Application Numb	ner [	PCT/	US97/38842		and was emended on		-	(8)	(applicable)
	h mandad abada blacel	( have ex	wines	t and undersial		(MM/DO/YYYY) tents of the above identified spec	eitestion.	including	the daims, as	amended by
l hei	any amendment a administration the reply claim foreign enter's cartificate,	duty to a priority in §385(;	y reten Esclosi Sensiti 2) of 20	e information w s under Title 35 ty PCT internal	hich is ma	tents of the above identified spar- tenal to patentiability as defined in tales Code § 118 (a)-(d) or § 360 cellor which designated at least	n: Title 37 (b) of any one coun	Code of foreign a try other tent or in	Federal Regula	ations, § 1.56 or patent or i States of
l hei	acknowledge the reby claim foreign sator's certificate, erics. Rated below international appl	eclicality to a priority to grand have leading the	y reten Esclosi Sensiti 2) of 20	e information was sunder Title 35 by PCT information information filting date before the state of the state o	hich is ma	tents of the above identified spectrenal to patentability as defined intakes Code § 118 (a)-(d) or § 366 certion which designated at least ting the box, any foreign application application application on which promity in	n Title 37 i(b) of any one countion for pass claimed	Code of foreign try other tent or in	Federal Regula application(s) fi than the United ventor's certific	ations, § 1.56 or patent or 3 States of ate, or of any
l hei inve Ame Pot	any amendment a administration the reply claim foreign enter's cartificate,	eclicality to a priority to grand have leading the	y reten Esclosi Sensiti 2) of 20	e information w s under Title 35 ty PCT internal	hich is ma	tents of the above identified spar- tenal to patentiability as defined in tales Code § 118 (a)-(d) or § 360 cellor which designated at least	n Title 37 i(b) of any one countion for pass claimed	Code of foreign try other tent or in	Federal Regula application(s) fi than the United ventor's certific	elione, § 1.56 or patent or i States of
l hei inve Ame Pot	any amendment is admosfedge the reby distin foreign entor's certificate, entor, listed below international appl Prior Foreign Appli	eclicality to a priority to grand have leading the	y reten Esclosi Sensiti 2) of 20	e information was sunder Title 35 by PCT information information filting date before the state of the state o	hich is ma	tents of the above identified spectrum to attendability as defined interest Code § 119 (s)-(d) or § 366 cellon which designated at least day the box, any foreign application on which provity.  Foreign Filing Date	n Title 37 i(b) of any one countion for pass claimed	Code of foreign try other tent or in	Federal Regulation (s) for the United Ventor's certified Contributed Contrib	elione, § 1.56 or patent or i States of late, or of any opy Altsched
I heringer	any amendment is administration foreign repry distint foreign enters, fissed below international appl Prior Foreign Appli Number(s)	pecifically duty to a priority i priority i and hav- ication cartion	y release berneith a) of an a sisce aring a	e information will be supported by PCT information when below filling date before Country	and the contained in th	tents of the above identified spectrenal to estensiability as defined intention Code § 118 (a)-(d) or § 366 cellon which designated at least drig the box, any foreign spectra the application on which provide (MM/DDMYYY)	n Title 37 si(b) of any one countion for pass claimed Price Not Cl	Code of foreign try owner tent or in	Federal Regult application(s) in than the United ventor's certific Certified C	olione, § 1.56 or patent or j States of arte, or of any
I herinve	additional foreign additional foreign additional foreign Additional foreign Additional foreign	pecifically duty to a priority i priority i and hav- ication cartion	y reterminations of the second	e information will be supported by PCT information when below filling date before Country	and the con- statch is ma- in United S ional appli in, by check we shat of	tents of the above identified spectrenal to patentiability as defined intention Code § 118 (a)-(d) or § 36t cellon which designated at least drig the box, any foreign spectra the application on which provide freeligh Filing Date (MM/DDM*********************************	n Title 37 si(b) of any one countion for pass claimed Price Not Cl	Code of foreign try owner tent or in	Federal Regult application(s) in than the United ventor's certific Certified C	olione, § 1.56 or patent or j States of arte, or of any

Burriers Hour Statement: This form is estimated to take .4 hours to complete. These sits vary depending upon the needs of the individual cable. Any comment is time you are required to complete this form should be sent to the Chief Information officer, Patient and Trademark Office, Washington, DC 20231 DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO Additional Commissioner for Palanta Washington, DC 20231

FROM

(TUE) G8. 01 CO 12:03/ST 12:00/NO. 3531892125 P 8

Theretay dain the benefit under 19th 35, United States Code § 120 of any United States applications), it § \$4500 of any PCT International application designating the United States of America, felted notes and Newton as the subject intelline over one to the product of the prod	DECLA	RATION						Page	2			
Auditional U.S. or PCT Informational application numbers are fisher on a supplemental pricing anest insuched heavilo.  As a named inventor, it issuely appoint the following absormary in such and application and to translate all business in the Plasma of Trademark Office contracted thumbers.    Finn Name	application dealgrating the United Statement disclosed in the prior United Statement S	States of PCT in	rice, Keled Sel Sematonal ap	iom end plicatio	i, impoist as the In in the market referiel to pairs	DLDNIGGE STIDINGS STIDINGS I	nese : by t a defi	r of each of i he liest perex ned in Title :	me claim graph of 37. Code	is of this Title 35. of Fede	appacaus Linko St al Regula	n is atas atans
As a named invantor, I ineraby appoint the following altermany(s) and/or agent(a) to prosource this application and to transect all business in the Patent and Tredemark Office connected therewire.    Firm Name		E.							Pare			
As a named invantor, I ineraby appoint the following altermany(s) and/or agent(a) to prosource this application and to transect all business in the Patent and Tredemark Office connected therewire.    Firm Name									4.			
Firm Name	As a named inventor, I hereby ap	point the foliox	ing attomsyls						***		uslneas ir	the
List ettomory(s) and/or agen/(s) name and registration number below:    Name	(v) Flam Name			SS P.	C.				re!			
Name Number Numb		ri(s) name and	registration ru	umber i	selow:			-		<b>,</b>		
ZINGER, DAVID F.  GROSETH, CRAIG C.  31,713 HANSEN, LEWIS D.  33,005  KOVARIK, JOSEPH E.  33,005  BLAKELY, TODD P.  31,328 SWARTZ, DOUGLAS W.  37,739  CONNELL, GARY J.  CROCK, WARNELL M.  32,020 KIRCLER, BRUCE A.  38,942  39,617  CROCK, WARNELL M.  CROCK WARNELL ROGERT R.  39,617  CRISTORY J.  CROCK WARNELL M.  CROCK WARNELL ROGERT R.  CRISTORY J.  CROCK WARNELL M.  CROCK WARNELL ROGERT R.  CRISTORY J.  CROCK WARNELL M.  CROCK WARNELL ROGERT R.  39,617  CROCK WARNELL ROGERT R.  CRISTORY J.  CROCK WARNELL ROGERT R.  CRISTORY J.  CROCK WARNELL M.  CROCK WARNELL	Name	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				B	isme			R		r
GROSETH, CRAIG C. 31,713 HANSEN, LEWIS D. 35,536 TOMPKINS, MICHAEL L. 30,860 KOVARIK, JOSEPH E. 33,005 BLAKELY, TODO P. 31,326 SWARTZ, DOUGLAS W. 37,739 CONNELL GARY J. 32,020 KURLER, BRUCE A. 38,942 CROCK, WANNELL M. 31,071 BRUNELL ROBERT R. 39,617   ☑ Additional attomety(s) antifor agant(s) named on a supplemental street attached hereto  Please direct all correspondence Louistomer Number or label  Name JOSEPH E. KOVARIK  Address 1560 BROADWAY, SUITE 1290  Additional attometic made hereth of my own knowledge are true and that all statements made on sitematic and belief are believed to be true; and further that these statements were made with submovinger that wifful false statements and the like so made are believed to be true; and further that these statements were made with submovinger that wifful false statements and the like so made are believed to be true; and further that these statements were made with submovinger that wifful false statements and the like so made are believed to be true; and further that these statements were made with submovinger that wifful false statements and the like so made are believed to be true; and further that these statements extended to be true; and further that these statements were made with submovinger that wifful false statements and the like so made are believed to be true; and further that these statements were made with submovinger that wifful false statements and the like so made are believed to be true; and further that these statements were made with submovinger that wifful false statements and the like so made are believed to be true; and further that these statements were made with submovinger that wifful false statements and the like so made are believed to be true; and further that these statements were made that such wifful false statements and the like so made are believed to be true; and further that these statements were an extended to be true; and further that these statements were an extended to be true; and further that the statements were an extended t			29,12	7	STAVISH, S	ABRINA	CRO	WLEY				
TOMPRINS, BICHAEL 31.328 SWARTZ, DOUGLAS W. 37.739 SLAKELY, TODO P. 31.328 SWARTZ, DOUGLAS W. 37.739 SLAKELY, TODO P. 31.328 SWARTZ, DOUGLAS W. 37.739 SLAKELY, TODO P. 31.329 SLAKELY, TODO P. 31			31,71	3	1							
CONNELL, GARY J 32,020 KIRCLER, BRUCE A 38,942  CROCK, WANNELL M 31,071 SRUNELLI, ROBERT R. 39,617    Additional automacy(s) and/or agam(s) named on a supplemental street attached here to    Please direct all correspondence	TOMPKINS, MICHAELL				1							
CONNELL (ARY)  CROCK, WANNELL M  31.071 SRUNELLI, ROBERT R.  39,617    Residence and correspondence   Customer   Number of the specific of the	BLAKELY, TODO P.				1							
Additional attorney(a) and/or agant(a) named on a supplemental street attached hereto  Please direct all correspondence   Customer   Number or label   Numbe	- · · · - · · · · · · · · · · · · · · ·		1		à							
Please direct all correspondence Customer Number or baried address below  Name JOSEPH E. KOVARIK  Address 1580 BROADWAY, SUITE 1200  Address 1580 BROADWAY, SUITE 1200  Address City DENVER State COLORADO Zip 80202-5141  City DENVER (333) 853-8700 Fax (333) 853-8700  It hereby declare that all sistements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are believed to be true; and further that these statements were made with the knowledge that willful false statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements may jeopardice the waldity of the application or any patent leased thereon.  Name of Sole or First knownitor:  Given Mark Middle Family McLaughlin Suffix Inventor's Segnatura  Residence City Baton Rouge State Lessians Country USA Citizenship USA  Post Office Address State Louisiana Zip 70808 Country USA Applicant Authority							. 17,	<del></del>				
Address ISGC BROADWAY, SUITE 1200  Address CRY DENVER State COLORADO Zip 30202-5141  Country UNITED STATES OF AMERICA Telephone (303) 863-8700 Fax (303) 853-0223  I hereby declare that all sixtements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that wilful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1081 of This 16 of the United States Code and that such writful false statements may jeopardize the validity of the application or any patent issued thereon.  Name of Sole or First Inventor:  [A pelibon has been field for this unsigned inventor inventor.]  A pelibon has been field for this unsigned inventor.  [Bluen Name Mark Middle Family Name McLaughlim 9.g. Jr.]  Inventor's Signatura  Residence City Baton Rouge State Louisians Country USA Citizenship USA  Post Office Address  State Louisians Zip 70808 Country USA Applicant Authority	Please direct all correspondence	Cu Nu	stomer inter or	PE NAME	2 (30) anno 23	0,410	1	)R 🗆				
Address   1560 BROADWAY, SUITE 1200    Address   State   COLORADO   Zip   30202-5141    City   DENVER   State   COLORADO   Zip   30202-5141    Country   UNITED STATES OF AMERICA   Telephone   (303) 863-8700   Fax   (333) 853-0223    I hereby declare that all sixtements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that wilful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 16 of the United States Code and that such wilful false statements may jeopardize the validity of the application or any patent issued thereon.  Name of Sole or First Invantor:   A perition has been fixed for this unsigned inventor    Given   Mark   Middle   Family   MicLaughlin   Suffix   9.9, Jr.    Inventor's Signatura   Date    Post Office Address   5514 S Pointer Court    Post Office Address   State   Louisiana   Zip   70806   Country   USA   Applicant   Authority	Name JOSEPH E.	KOVARIK		·								
Address  City DENVER  Country UNITED STATES OF AMERICA  Telephone (303) 883-9700  Fax (303) 863-0223  I hereby declare that all sistements made herein of my own knowledge are true and that all statements made on afformation and belief are believed to be true; and further that these statements were made biff the knowledge that willful false statements and the like so made are believed to be true; and further that these statements were made biff the knowledge that willful false statements and the like so made are believed to be true; and further that these statements were made biff the knowledge that willful false statements and the like so made are published by five or imprisonment, or both, under Section 1081 of Title 16 of the United States Code and that such writtul false statements may pattern be such as been filed for this unsigned inventor.  Name of Sole or First Inventor:  [A pelibon has been filed for this unsigned inventor  [Bluen] Name Mark  Inventor's Signatura  Residence City Baton Rouge  State Louisians  Country USA  Citizenship USA  Post Office Address  City Baton Rouge  State Louisians  Zip 70808  Country USA  Applicant Justicinty  Authority		DADWAY, SU	TE 1200									
City DENVER  Country UNITED STATES OF AMERICA Telephone (303) 883-8700 Fax (333) 853-0223  I hereby declare that all sistements made herein of my own knowledge are true and that all statements made on enformation and belief are believed to be true; and further that these statements were made with the knowledge that wilful false statements and the like so made are burnished by fine or Imprisonment, or both, under Section 1001 of This 16 of the United States Code and that such writful false statements may jeopardize the validity of the application or any patent issued thereon.  Name of Sole or First Inventor:  A perition has been filed for this unsigned inventor  Given Name Mark  Inventor's Signatura  Residence City Baton Rouge State Louisians Zip 70808 Country USA Citizenship USA  Post Office Address  State Louisians Zip 70808 Country USA Applicant Authority	Acdress											
Inerety declare that all statements made harein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that wilful false statements and the like so made are burishable by fine or imprisonment, or both, under Section 1081 of This 16 of the United States Code and that such writful false statements may journation the validity of the application or any patent issued thereon.  Name of Sole or First inventor:    A petition has been filed for this unsigned inventor	CRY DENVER						COL					
Name of Sole or First Invanion:    A petition has been filed for this unsigned inventor	I hereby declare that all statement believed to be true; and further the	nts made here had these store ent. or both, un	in of my own k ments were m	nowled ade will 301 of 1	ge are true and h the knowledge 19e 16 of the Un	that all a	itul ita	vents made:	on enform	ration an	d belief 2 made 20	188 4 4
Name Mark initial Name McLaughlin e.g. Jr.  Inventor's Signatura  Residence City Baton Rouge State Louisians Country USA Citizenship USA  Post Office Address 5514 S Pointer Court  Post Office Address State Louisians Zip 70806 Country USA Applicant Authority	Name of Sole or First Inventor:				^_^^^^^^^^^	petition	has b	ean filed for	this unsi	ignad inv	entor	
Inventor's Signatura  Residence City Baton Rouge State Louisians Country USA Citizenship USA  Post Office Address 5514 S Pointer Court  Post Office Address City Baton Rouge State Louisians Zip 70806 Country USA Applicant Authority	1					McLau	hibr					
Residence City Baton Rouge Size Editions State Edition Rouge  Post Office Address    City Baton Rouge	Inventor's			<u>,</u>								
Post Office Address  City Baton Rouge State Louisiana Zip 70808 Country USA Applicant Authority	Residence City Baton Roug	e	State	Louis	ane	Countr	y   L	ISA	Citta	enship	USA	
City Baton Rouge State Louisiana Zip 70806 Country USA Applicant Authority	Post Office Address 5514 S	Pointer Cour	t									
City Baton Rouge State Louisiana Zip 70806 Country USA Applicant Authority	Post Office Address											
The table and the property of secretary and specific services.		State Lo	xuisiana	7ip	70808	Cos	entry	LISA				<u></u>
			enelpepanist si		attached hereko	<del></del>						

See Notes to the request form

(TUE) 08 01'00 12.03/87.12:00/NO.3561892125 P 10

Type a plus sign (+) inside this box + ADDITIONAL INVENTORIS) DECLARATION Supplemental Sheet A petition has been filed for this unsigned inventor Name of Additional Joint Inventor, if any: Family a.g. Jr. Name Sohneck, Jr. Karl Name Oste inventor's Signature Citizanship USA USA Pennsylvania Country Residence City 3099 Survice Lake Post Office Address Post Office Address Applicant USA Ponnsylvania 200 18337 Country Millard State A petition has been filed for this unsigned inventor Name of Additional Joint Invertor, if any: Suffix Middle Family Initiat e.g, Jr. Name Date Signature Citizenship State Country Residence City Post Office Address Post Office Address Applicant Authority Country Ζiρ 31414 City A petition has been filled for this unaligned inventor Name of Additional Joint Inventor, If any: Suffix Michigle Family Given initial Hame e.g. Jr Name Date inventor's **Signature** Chizenship State Country City Post Office Address Post Office Address Applicant Country Ζŀρ Grate City Authority A polition has been filed for this unsigned inventor Name of Additional Joint Inventor, if any: Middle Pagraly Given e.g. Jr. Name initia: Name Dete inventor's Signature Citizenship State Country Residenc City Post Office Address Post Office Address Applicant Country Zio City Authority

[ ] Further applicants and/or (further) inventors are indicated on another continuation sheet Form PCT/RO/101 (community sheet)(July 1998)(form duplicated by Sheridan Ross P.C.-jmm)

Type a plus eign (+) imido tris box •

**DECLARATION** ADDITIONAL Endfor AGENT INFORMATION
Supplemental Steet

1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-		- and and a second	NEG!
Name	Registration Number	Name	Registration Number
HUGHES, RICHARD L	31,264		
HARSRA, TEJPAL S.	35,172		
HARTJE, GANA ),	47.538		1
DALLAS PEDRETTI, ANGELA 1)ES, BENJAMIN S	42,450 42,801		
KNEPPER, BRADLEY M.	44,189		
BROWN, THERESA A	32,547		
Druxman, Miriam R Duffray, Denous J.	42.499		
portone, ocipe23.	45,299		
	1		]
			1
	1		1
			1
	1		1 1
			1
			1
			1
			1 1
			1
	<del></del>		

nang Késtit þi Þoniiaet čn."

AND O.D. I

PTO/SB/01 (\$-95)
Approved for use through 10/31/08 CMB 0651-0032

Abs	a plus sign (+) India	le this b	ot [	3	Palent and Trade	mork Office: U.S.	DEPARTMENT OF COMMERCE
-	PTO . 6/05			ment of Consucres	Attorney Dockes Number	3	590-3 PUS
					First Named Inventor		CLAUGHLIN, Mark
	DECLA				œ	MPLETE IF KNO	ww
	רועווט				Application Nation		
	PATENT	APP	LIC	ATION	Filing Dire		
	Declaration	OR	-	Onderator	Group Art Unit		
×	उध्धानमञ्जूष जाका राजधिज्ञं निर्मालक			उत्तरमधित्ये <b>स्टाब</b> मिर्ग्येन स्थित्य	Emire Name		
n t	believo I am the ori	ifficaci sud girani, tu	drosa, s Calenda	and editensing are s opin inventor (Finally	s stated delow year to my name out hither in (stad below) or an en	ginal, Gracered John	i inventor (5 photal rumos are
					inch a pilon is suight on the line MEDIA DEVICE AND MET		HEREFOR*
					(१६७ व कि investion)		Ì
	pedilanion of which to algebrai forms GR was lifed on (MM/2D17777)		0	5 Junes 19 <b>67</b>	as United States Application	Number or PCT to	( <del>Gringligna</del> )
	(MACOUITYTY)		<u>_</u>	<del></del>	لــــ		
•	Application Number		CTAU	597/08942	and was amended on [WANDOPYYY]		(# applicable)
2	भू अक्रकाचेत्रस्था इस्ट	orically :	Blanke	Shore	omiunes of the above identified spe		
,	solumented pe this di	ny to die	ricec b	niamenan etiet is i	गर्यक्तां के इस्कारक्रिए का ईस्त्रील्स ।	n 145e 37 Code of	Federal Rogulations, § 1.55.
TVE	Maria centricato, or ( tear flates) below an		of any i	PCT è dentrationes so mittes accore, by cité	: Status Code († 110 (a)-(d) or († 36) plicoton which designated at Icasa ciding the Bon, any foreign applicat at the spolication on which priority :	one country piner	then the Linkop States of
	or Foreign Applicat			Gountry	Foreign Filing Date (MADD/YVVV)	Priority Nor Cigured	Certified Copy Attached?
							Yes No
	Molional foreign a	ا مخبهنادور	as agradija	lers are luthed on a s	oppiemental provity shaet attached	T	
mark	by cases the benefit	Cunder	Title 35	, United States Costs	§ 119(c) of any United States pro	visional applicator	(6) (figures projects
	Application N		<del></del>		ing Date (MACOUTYTY)		
50-04	D.724	·		Misrch 14,	1987		Additional provisional appleasion numbers are listed on a supplemental provity shoot altached iterato.

Emotion Paper Substructors This form as an emotion to take . A hours or computer. These will savey describing cause the records of the interval date. Any appropriate on the emotion of their paper are required to compute the form already to the Cloud advantations officer, Pages I and Tradeways, Office, Washington, Office, the paper of the page of the Control of the

a: 25 0; 11;22;

303543 7313 => MCCASKILL ; #5

Wednesday, August 02, 2000 11:37 AM

James Weldon 303543 7313

FROM

(TUE) 08. 01' 00 12:03/87. 12:06/NO. 3561892125 P 8

Type a plus si	gn (+) mside	e this bo	) × ×												
	D	ECL	ARA	TIO	N _							Page	2		
application of not disclose Code § 112.	insignating ( ) in the prior ) actropolog	fre Linkes Funktes ága tha	ad State States duty to	s of Am of PCT Inclose	urica, Sab Internatica informati	nd berts nd appl on which	ir und, 1 Icalian I Ir is mai	rapiares In the mac ledal 19 pi	the : war	subject posuide lability (	retter of d by the l is defined	decili of Brut pera t in Tide	ine cial graph o 37. Cod	me of Fine la of F	iT international this application s Jis. Linked Stubs edecal Regulation of this application
	rent Applica Number	<b>Hig</b> ro	T	i	PCT Pare Number					rd Filing MDD/Y			Pe		Mitht Number Optication)
													7		
Additional Asia nemedi Patent and T	nventor, I to	entry a	opoint if	e folio-	drau 250 der										if business or the
First N	₹ [	*****			RIDAN						Cimton Number	or labo	• [	-	· · · · · · · · · · · · · · · · · · ·
List att	אונ (פ) אוני	Mor age	ent(s) ne	me and	registratio	IN TRUME	er belo	W.							
	Nervi					iration mber				Ng	Fire		7		Registration Number
ZINGER, DAI GROSIETH, C					_	,127	•	TAVISH,			ROWLE	٧	T		33,374
TOMPKINS.		_			-	713		iansen,							35,538
BLAKELY, TO		•		- 1		326		(CVARIK, KWARTZ,	– .		-				
CONNELL G	-					020	t	UGLER			<b>27</b> ,				37,739 38,942
CROOK, WA				1		G71		RUNELL	, RC	BERT	R.				19,617
Additional	(w)v(m)	Bridfor :	<b>201</b> (8)	ached	on a supp	101710110	of Street	#Sapted	hen	do					
Places direct :	я сопивро	ndençe			ber or	T			-		OR		Fil in	Chros Se bek	pondence W
Name	JOS	EPH E.	KOVAR	K_							1		<del></del> -		~~~~~~
Address	15	OC BAX	ALIMA	r, 8UIT	E 1200							<del></del>			
Address: DI														<del></del>	**************************************
يتبهاب خت	IVER		******					Stat		Q	DLORAD	0	Zış	, 8	0202-5141
						lephon.		G3) B63-0	700			Fax	(300	L88 (I	0223
I haraby dada believed to be punishable by may jespartize	fine or imon	Cale Ser	at ar hai	h wade	· Cardina	4004	The of		timi o ika Nime	af stat L'utilis States	oments n faise sta Code un	nede on d lemente d that so	and the cit willi	Mon an Nice s of feight	id belef are o made are distantante
Manne ut Sido :									pati	hon has	been Re	d for the	(alajan	act inv	entor
Name Merk		<del></del>			inite:			arety isrie	Mc	augintin	:		,		Buffex
	Mar		1.1	M	7	ż					0ate 9161	00	·		
Residence City					State	Louis	fene	LA	Cou	nay	USA	T	Cilizani	thip:	UBA
Vest Offices Add		514 B. F	'वर्षस्का (	OUN					_			<del>-</del>			
Post Office Add	rees								_	·			·		
Zity Reston R	ande	]	State	Louisk	ma	Zip	70806	)	To	Country	USA	1	Appli		T
													<u> </u>	<del>~'</del>	

28 Additional inventors are being named on supplemental sheeks) attached hereto.

FROM LAW/OFFICE 3037942073 8-03-200 9:41PM ARNOTE SOUTH OF BOKEPHOLI SOUTH OF THE CONTINUE OF THE SOUTH DOVESTOR TRAIN STRANGE TO THE TRAINING Type a plus sign (+) Inside this box . . ADDRIGHAL DEVENTURES) DECLARATION Supplemental Elect Name of Additional Joint Inventor, if any A potition has been filed for this unargined inventor Middle Ferrit Kuny Name Marine (TE) Lactoite -g. jr STRINE Hatidenes City Cupertino CaMpove والمدرجهات Country USA USA State Para Office Address 1095Z Savance Orive Post Office Address Applicant Authority California USA State 95019 COUNTY <del>ದಿವಾರಗ</del>ು ΖÞ Name of Additional Joint Inventor, if any. To the sengiare sale will bear seed used noting A **Riberiti**o Fastilly गयहरू Name 2.g. Jr 8/3/2007 APLI Residence Littleton Serie Colorado USA Citizenship: City Poer Other: Address 5680 W. Rowlerst Avc. Post Office Adds Applicant Linieton Colorado MD120 USA Ζφ Authority Name of Additional Joint Inventor, if any: A petition has been field for this uneigned inventor Suffee NGCO'e knittet Fishin James Name: Weston eg. Jr Name <u>Claim</u> invector's Signature Cheer with USA Sure Colorado . Country Residence City Boulder Fast Office Address 6424 S. Boulder Road Post Office Address Applicant 90303 USA Boulder 5tde Cobsesso Zφ Сошил Chy Authority Name of Ademonal John Inventor, if any: A patition now been state for this unsigned inventor Michigan Given Family Name J. Bradford (halla) METY e.g. #, Signature

State

Mary Carrie

💢 रिप्तिक अभूगेकाम् अर्थिक (विश्ववेद्य) अभ्योगिक अन्य निर्माणको एवं २२०वेद्य देवसंभाविक अंधिक

Form PCT/RO/101 (communication about/Only 1996)(form deplicated by Shorston Ross F.C. 4940)

מושועושונו

21453

USA

UŞA

Ottomenio.

Applicant Authority

USA

See Notes to dur request form

Country

Country

Residence City

Paul (Mico Address

Post Office Address

Annualis

A:mepails

63 Gentry Court

See Noves to the request form

		D	DECLA	RAT	ION					٨	DOMNOWAL Suppleme			
Name o	7 Addisc	<b>JD</b>	nt liverity	, If pary;	T				_	_ Apro	ton has been	i i i i	for this was	pred in
Green	T.					Middle		Family		Sahneck, J	,		•	
· / - M	I Kep								1		T		1	
inverte Signatu											Date			
(Carlog	uce Cris	M	April .			State	Perst	piereta	4	Country	LIBA		Citabrerie	UBU
Post O	Name Acto	-	3099 \$4	urige Lai	re-									
Pust O	ROE AUG	442												
City	Miller			Sale	Pam	yr-enia	750	75237		Country	USA		Authority	Ţ
P	d Adddin	نط ادر	तः श्वास्त्राच्या	, if are:	1					∏A med	ion has here		le the wid	gnod ir
Given	1				_1	Madde		(Care					7	Suffix
Nevne	<u> </u>					Inita		Name			1	1		8.4). Jr
invento Signale											Date	1		
							· -				<u> </u>	1	7111	т —
Reside City		ł				State	1			Country		- [	Cilizanehip	
	Mes Add	-			<u></u>									
Past D	Rice Add	-												•
CD's				S##			ΖÞ			Country			Applicant Authority	1
Name (	A AJON	نجل اس	est Mondate	H ony.	Т	#* <del>1.</del>			-	<b>□</b> A p=0	ion has bee	n Dies	for this unsi	gned i
GENER	Ţ		<del></del>			Michael Services		Farel						
Mapre	+				<del></del>	1 31,440						T		
Danig Supres											Date			
-											]	<u> </u>	, <del></del>	
Rende	esc <del>e</del>			····		500				Country			CIPREMEDIA	
City Post O	Nos Act	PAS.								<u> </u>	-J			<u> </u>
	Mac Add													
City				Serie			ZÞ			Countr	,		Applicant Authority	
niame.	or areful	(c	ing Inventor	i dene	<del>\</del>	<del>;;=,;=</del> =			_	TARE	Con has bee	n Med	for this una	lgried i
Ghen	1		.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		<u> </u>	Midd	io !	Pan	y	1			1	Suffre
Name						37/E2		76.mm	2	<u> </u>	1	1		<b>849.</b> J
invent											Dete	1		
2 hay	and													Suffix B.g. Jr.  Suffix B.g. Jr.
										,		┸~		7
Reside	NC Day	1				State	1			Country		- }	Citizenship	1

Form PCE/RG/101 (commonturates) (Daty 1998) form deplicated on temples continuation short.